

MAR 30 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>33W</u>	<u>D-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 25th DAY  
FEBRUARY A.D. 2000 AT 10:30 A.M. A  
RECORDED IN LIBER 5 OF LAND CORNER  
RECORDATION RECORDS ON PAGE 70.

*Nelda Bishop*

BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Michael Mileski, in a field survey on July, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-5; One-quarter Corner common to Sections 8 and 17, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1849 and monumented with a sugar maple post witnessed by a Sugar 18 N72°E 34 lks. and a Yellow Birch 16 S37°W 16lks.

No evidence of subsequent restoration was found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-5; One-quarter Corner common to Sections 8 and 17, T52N, R33W;

No physical or record evidence was found bearing upon the location of this corner. Reestablished the corner midway and on line between the NW corner of section 17 and the NE corner of section 17. The physical centerline of Niemi Road is very nearly on a direct line from this corner so established to the N¼ corner of section 8.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-5; One-quarter Corner common to Sections 8 and 17, T52N, R33W;

Set a 1" (I.D.) X 36" galvanized iron pipe with cap four inches below the ground.  
This corner falls in a small field.

Set 7" spike	N/side	10" Black Ash	N75°E	107.44'
Set 7" spike	N/side	10" Aspen	S88°W	77.29'
Set 7" spike	SW/side	12" Red Maple	N59°W	79.94'
		Right bank of Sturgeon River	South	180'
		6' Steel fence post w/ yellow sign	North	1.0'

All of the above new bearing trees were marked with upper and lower blazes. The lower blaze was scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Baraga County

12-16-99  
*[Signature]*



Signed by *[Signature]*  
Surveyor's Michigan License No. 39091

Date 27 Dec 1999