

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Baraga Located In: Corner Code #
 (County)

1. Public Land Survey T 52N R 33W D-9
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

RECEIVED FOR RECORD THIS 14TH DAY C
 JANUARY A. D. 1999 AT 10:30 A. M. A
 RECORDED IN LIBER 5 OF LAND CORNER
 RECORDATION RECORDS ON PAGES 20-21.

Hilda Bishop
 BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Michael Mileski, in a field survey on September, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9				●									
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-9; One-quarter Corner common to Sections 20 and 29, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1849 and monumented with a cedar post witnessed by a Cedar 9 N18°W 10 lks. and a Tamarack 12 S76°E 8 lks. This corner was remonumented with a 1" diameter iron pipe and 4" aluminum cap on 26 July 1965 by Frank Bray of the Michigan Department of Conservation. Mr. Bray set the monument at the base of an "old wood post and new post, which check with Tamarack stump with notch and part of scribe marks, original BT". Refer to the Land Corner Record recorded in Liber 2, page 304, Baraga County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-9; One-quarter Corner common to Sections 20 and 29, T52N, R33W;

See back of form.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-9; One-quarter Corner common to Sections 20 and 29, T52N, R33W;

Left existing Michigan Department of Conservation monument in place.

Set 7" spike	NW/side	12" Balsam	N20°E	43.76'
Set 7" spike	W/side	18" White Pine	S17°E	42.02'
Set 7" spike	N/side	16" Cedar	S40°W	24.82'
Set 7" spike	N/side	13" Black Spruce	S71°W	41.34'
		6' Steel fence post w/ yellow sign	North	1.5'

All of the above new bearing trees are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.



Signed by *Michael Mileski*
 Surveyor's Michigan License No. 39091

Date 28 Dec 1998

APPROVED LAND CORNER
 P.A. 345 OF 1990
 Baraga County

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

12-17-98
202

LIBER 5 PAGE 20

REVISED MAY 14, 1975
 REVISED JAN., 1983
 REVISED OCT., 1995

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-9; One-quarter Corner common to Sections 20 and 29, T52N, R33W;

Found a 1" diameter iron pipe with a broken 4" diameter aluminum cap projecting 22" above ground as set by Mr. Bray. This monument was found set at the base of an old cedar post six feet in length and approximately 4" in diameter squared at the top with the number "20" scribed on two sides and the number "¼" scribed on one side. Mr. Bray noted the following accessories:

12" Cedar S82°E 9 lks. (5.94')
Presently alive and 17" in diameter having a 3.5 foot long, mostly open, lower blaze with illegible scribing.
Measured S85°E 6.3' to face

14" Yellow Birch N40°W 40 lks. (26.4')
Found standing dead and 16" in diameter having mostly open upper and lower blazes. The upper blaze is scribed "¼ S" and the lower blaze is scribed "NBT".
Measured N36°W 26.2' to notch at face

The following local new bearing tree established by persons unknown was observed:

Found a 14" diameter cedar stump 36" tall having an unscribed lower blaze with a distinct chaining notch.
Measured N72°W 5.1' to notch at face

Accepted as the best available evidence of the position of the original corner.