

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>33W</u>	<u>D-11</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECEIVED FOR RECORD THIS 14TH DAY OF JANUARY A. D. 1999 AT 10:30 A. M. AND RECORDED IN LIBER 5 OF LAND CORNER RECORDATION RECORDS ON PAGES 22 - 23.

Relda Bishop
 BARAGA COUNTY REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Michael Mileski, in a field survey on September, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-11; One-quarter Corner common to Sections 29 and 32, T52N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-11; One-quarter Corner common to Sections 29 and 32, T52N, R33W;

The iron bar described by Mr. Destrampe was probably removed by road improvement. Using the C/4 corner and the NW and SE corners of the 5 acre parcel, this corner was reestablished in accordance with Mr. Destrampe's survey. The only remaining 1973 accessory fits well with this position (see Part A). This position is 1.1 feet north of the physical centerline of Sturgeon Road. An old fence runs south. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-11; One-quarter Corner common to Sections 29 and 32, T52N, R33W;

Set a 1"(I.D.) x 36" galvanized iron pipe with cap. This monument was set 12 inches below the asphalt. The 8 inch diameter asphalt opening was filled with 6 inches of MDOT-furnished CP-7 material. A 7" spike was set at the surface directly above the iron pipe monument.

Set 7" spike	NE/side	12" Sugar Maple	S50°E	84.09'
Set 7" spike	NE/side	11" Sugar Maple	S39°E	64.63'
Set 7" spike	E/side	11" Sugar Maple	S11°E	55.42'
Set 7" spike	S/side	14" Apple	N80°W	187.04'
		6' Steel fence post w/ yellow sign	S05°E	42.0'

The apple tree was not marked or painted. All remaining bearing trees were marked with upper and lower blazes. The lower blaze was scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.



Signed by *Michael Mileski*
 Surveyor's Michigan License No. 39091

Date 28 Dec 1998

APPROVED LAND CORNER
 P.A. 345 OF 1990
 Baraga County

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

12-17-98
Rll

LIBER 5 PAGE 22

REVISED MAY 14, 1975
 REVISED JAN., 1983
 REVISED OCT., 1995

A. Description of original monument and accessories and/or subsequent restoration:

D-11; One-quarter Corner common to Sections 29 and 32, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1849 and monumented with a hemlock post witnessed by a

Cedar 9 N72°W 25 lks.

and a

Sugar 12 S50°E 20 lks.

On page 4 of the Baraga Township Highways Journal, the centerline of the Keweenaw Bay and Otter Lake Road (presently known as Sturgeon Road) was described as passing through this corner (entry dated 30 August 1900). On page 52 of the Highways Journal, Louis Nicholson, County Surveyor, described a road (presently known as Cemetery Road) as beginning at the ¼ corner between sections 29 and 32 and running northwesterly. In 1973, Dennis Destrampe, PS #18993 recorded a boundary survey of a 5 acre parcel in the SW corner of the SE¼ of NW¼ of section 32. Mr. Destrampe's survey indicates the ¼ corner between sections 29 and 32 as a found 1½" diameter iron bar with the following accessories:

M.B.T. Pole North (Mag.) 21.00'
Gone

R.E.A. Power Pole S47°30'E (Mag.) 46.28'
Found cut off at 2.3 feet above ground and appears as though it may be slightly
knocked from the 1973 position.
Measured S47°E 46.63'

Mr. Destrampe's survey also tied to the Center ¼ corner of section 32 and is recorded in Liber 1 on page 17, Baraga County Records.