

**SURVEY & REMONUMENTATION**

FEB 23 1998

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>33W</u>	<u>E-1*</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 30TH DAY OF DECEMBER A.D. 1997 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGE 796

*Helds Backops*

BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Michael Mileski, in a field survey on 20 November, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-1; Section Corner common to Sections 4 and 5, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1845 and monumented with a wood post witnessed by a Tamarack 7 N51°W 13 lks. and a Tamarack 6 N58°E 13 lks.

During the subdivision of T52N, R33W, by William Burt, D.S. in 1849, this corner was further witnessed by a Tamarack 6 S49°W 21 lks. and a Tamarack 6 S30°E 23 lks.

No subsequent record evidence bearing upon the location of this corner was found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-1; Section Corner common to Sections 4 and 5, T52N, R33W;

This corner was considered lost and reestablished on line at the proportionate distance between the N¼ corner of section 5 and the NE corner of section 4. The N¼ corner of section 5 is an original U.S. corner. The NE corner of section 4 is probably an original U.S. corner. The corner position falls at the confluence of two ditches. One of which bears north and south and one of which bears only to the east. A witness corner was established on the section line at a distance of 45.00 feet westerly of the proportioned section corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1; Section Corner common to Sections 4 and 5, T52N, R33W;

The witness corner described in Part B was monumented with a 1" (I.D.) x 36" galvanized iron pipe and cap stamped as to location 12" below ground.

Marked with 4" letters "XBO" the west side of a steel bridge truss.  
 N26°E 58.88' (to center of X)

Marked with 4" letters "BXO" the east side of a steel bridge truss.  
 N49°E 80.59' (to center of X)

6' Steel fence post w/ yellow sign East 13'

Physical centerline of a north-south, 10' wide, gravel road. West 13'

\*This corner is also E-13 of T53N, R33W.

LIBER 4 PAGE 796



Signed by [Signature]  
 Surveyor's Michigan License No. 39091

Date 19 Dec 1997