

MAR 8 0 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>52N</u> R <u>33W</u>	E-5	
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____

RECEIVED FOR RECORD THIS 25th DAY  
FEBRUARY A.D. 2000 AT 10:30 A.M.  
AND RECORDED IN LIBER 5 OF LAND  
CORNER RECORDATION RECORDS ON  
PAGE 95 and 96.

*Fields Bishop*  
BARAGA COUNTY REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Michael Mileski, in a field survey on July, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-5; Section Corner common to Sections 8, 9, 16 and 17, T52N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-5; Section Corner common to Sections 8, 9, 16 and 17, T52N, R33W;

Found no existing monumentation at this corner. Reestablished corner by doubling the NE corner of section 8 over the E 1/4 corner of section 8. This position falls approximately on the physical centerline of a north-south, 30-foot wide drainage ditch. Established a witness corner on the section line 29.00 feet west of the section corner. This witness corner is located on the west high bank of the ditch approximately 15 feet west of the water's edge.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-5; Section Corner common to Sections 8, 9, 16 and 17, T52N, R33W;

Monumented the witness corner described in Part B with a 1" (I.D.) X 36" galvanized iron pipe and cap projecting four inches above the ground.

Set 7" spike	S/side	10" Sugar Maple	N83°E	3.25'
Set 7" spike	W/side	14" Yellow Birch	S06°W	30.67'
Set 7" spike	N/side	13" Red Maple	S77°W	40.81'
Set 7" spike	NE/side	5" Sugar Maple	N65°W	10.04'
		6' Steel fence post w/ yellow sign	North	1.0'

All of the above new bearing trees were marked with upper and lower blazes. The lower blaze was scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Baraga County

12-16-99  
[Signature]



Signed by [Signature]

Date 27 Dec 1999

Surveyor's Michigan License No. 39091

MAR 30 2000

SECTION

A. Description of original monument and accessories and/or subsequent restoration:

E-5; Section Corner common to Sections 8, 9, 16 and 17, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1849 and monumented with a sugar maple post witnessed by a

White Pine      6      S62°W      69 lks.

and a

Spruce          10      N68°E      25 lks.

In the Michigan Department of Natural Resources "Report of Survey - Arnheim Ditch, Sturgeon River Sloughs - Project No. 22-4028" dated 21 October 1971 from Arthur Enger, District Surveyor to John Nelson, Regional Engineer the following is stated:

"The best record evidence of the location of the existing north and south Arnheim Ditch is found in instrument recorded at the Baraga County Register of Deeds office in Liber 32 of Deeds, Page 460, wherein reference is made of the intention of the Houghton Land and Drainage Company, one of the parties, to construct its main drainage canal along the section lines between Sections 8 and 9 and 16 and 17, requiring a strip fifty feet wide on each side of the section lines. This deed is dated June 10, 1912."