

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>R33W</u>	<u>E-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 14TH DAY OF
 JANUARY A. D. 1999 AT 10:30 A. M. A
 RECORDED IN LIBER 5 OF LAND CORNER
 RECORDATION RECORDS ON PAGE 24.

Felda Bishop
 BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2			1
3													
4	7			8		9		10		11			12
5													
6	18			17		16		15		14			13
7													
8	19			20		21		22		23			24
9													
10	30			29		28		27		26			25
11													
12	31			32		33		34		35			36
13													

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Michael Mileski, in a field survey on September, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-10; One-quarter Corner common to Sections 28 and 29, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1849 and monumented with a sugar maple post witnessed by a Sugar 8 N56°E 19 lks. and a White Pine 36 S68°W 30 lks.

On page 11 of the Baraga Township Highways Journal, the following entry is written:

"Napoleon Gagner Road, Commencing at the corners of secs 28-29-32 x 33 Town 52 North of Range 33 West run north on sec line between (sic) secs 28 x 29 half a mile, James McMahan Township Clerk".
 This entry is not dated.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-10; One-quarter Corner common to Sections 28 and 29, T52N, R33W;

Reestablished corner in the centerline of a north-south, 20-foot wide, graded gravel road (Jarvi Road) and on the projection of old fences to the east and west. This corner is 25 feet west of a corner post having fences to the north and east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-10; One-quarter Corner common to Sections 28 and 29, T52N, R33W;

Set a 1"(I.D.) x 36" galvanized iron pipe with cap 12" below the road surface.

Set 7" spike	SE/side	6" Aspen	N68°E	78.12'
Set 7" spike	SW/side	12" Balsam	S37°E	36.27'
Set 7" spike	S/side	15" Red Pine	N83°W	53.20'
Set 7" spike	NE/side	15" Red Pine	N28°W	82.21'
		6' Steel fence post w/ yellow sign	West	25.0'

All of the above new bearing trees were marked with upper and lower blazes. The lower blaze was scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.



Signed by *Michael Mileski*
 Surveyor's Michigan License No. 39091

Date 28 Dec 1998

APPROVED LAND CORNER
 P.A. 345 OF 1990
 Baraga County

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975
 REVISED JAN., 1983
 REVISED OCT., 1995

12-17-98
DOL

LIBER 5

PAGE 2A