

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>33W</u>	<u>E-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 14TH DAY OF JANUARY A. D. 1999 AT 10:30 A. M. A RECORDED IN LIBER 5 OF LAND CORNER RECORDATION RECORDS ON PAGE 25.

Nelda Bishop
 BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Michael Mileski, in a field survey on September, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-11; Section Corner common to Sections 28, 29, 32 and 33, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1849 and monumented by a 12" diameter maple witnessed by a Hemlock 24 N28°W 17 lks. and a Hemlock 15 S12°E 21 lks. On page 4 of the Baraga Township Highways Journal, the centerline of the Keweenaw Bay and Otter Lake Road (presently known as Sturgeon Road) was described as passing through this corner (entry dated 30 August 1900). On page 11 of the Highways Journal, Napoleon Gagner Road (presently known as Jarvi Road) was designated to commence at this corner (entry not dated).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-11; Section Corner common to Sections 28, 29, 32 and 33, T52N, R33W;

APPROVED LAND CORNER
 P.A. 345 OF 1990
 Baraga County

12-17-98
[Signature]

Found a 1" x 24" iron rod at the physical intersection of Sturgeon Road and Jarvi Road. This monument was found 24 inches below the top of the asphalt. An old, mostly down, fence runs south from this monument a distance of 4800 feet to the north edge of Kelsey Creek. This fence was found to be within five feet of a direct line connecting this monument to the SE corner of section 32 (an original corner) at all nine points located. Accepted as the best available evidence as to the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-11; Section Corner common to Sections 28, 29, 32 and 33, T52N, R33W;

Replaced found monument with a 1" x 36" galvanized iron pipe with cap. This monument was set 12 inches below the asphalt. The 8 inch diameter asphalt opening was filled with 6 inches of MDOT-furnished CP-7 material. A 7" spike was set at the surface directly above the iron pipe monument.

Set 7" spike E/side	7" Aspen	N37°E	99.01'
SW corner of metal-sided addition to fr. hse.		S40°E	177.71'
Set 7" spike W/side	11" Apple	S04°W	40.05'
Set 7" spike SE/side	Power Pole	S35°W	37.76'
	6' Steel fence post w/ yellow sign	South	35.0'



Only the aspen NBT was blazed, scribed and painted. The power pole was marked with a vertical red paint stripe. The apple NBT was not marked or painted.

Signed by *[Signature]*

Date 20 Dec 1998

Surveyor's Michigan License No. 39091