

SURVEY
REMONUMENT

MAY 05 1996

CO.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>33W</u>	<u>E-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 23RD
DAY OF OCTOBER, 1996 AT 10:30
A.M. AND RECORDED IN LIBER 4
OF LAND CORNER RECORDATION
RECORDS ON PAGES 658 - 659.

Nelda McAntypa
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael Mileski, in a field survey on October, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-13; Standard Corner common to Sections 32 and 33, T52N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-13; Standard Corner common to Sections 32 and 33, T52N, R33W;

Reestablished this corner at a position consistent with the BLM position as determined in 1984. From this position a cedar stump hole approximately 12 to 14 inches in diameter is located at record U.S. bearing and distance. Also from this location, a raised mound of earth approximately 30 inches in diameter and very much resembling a stump is located at record U.S. bearing and distance. However, an excavation of this mound did not yield any wood fragments. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13; Standard Corner common to Sections 32 and 33, T52N, R33W;

Set a 1"(I.D.) x 36" galvanized iron pipe with a 2" aluminum cap appropriately stamped as to location.

Set 7" spike	S/side	10" Yellow Birch	S89°E	17.09'
Set 7" spike	NE/side	10" Red Maple	S64°E	63.94'
Set 7" spike	E/side	10" White Spruce	S16°W	37.78'
Set 7" spike	W/side	12" Red Maple	N18°W	29.74'
		C.C. Sec. 4 and 5	East	9.24'
		Location Post	South	1.0'

All of the above new bearing trees are marked with upper and lower blazes. The lower blaze is scribed "NBT SC". Both blazes as well as a band around the tree at the upper blaze are painted red.

Signed by Michael Mileski

Date 22 Oct 1996

Surveyor's Michigan License No. 39091

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County

10-09-96



A. Description of original monument and accessories and/or subsequent restoration:

E-13; Standard Corner common to Sections 32 and 33, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Hemlock 26 N60°E 12 lks.

and a

Cedar 7 N58°W 34 lks.

During the course of a survey conducted by Stephen Douglas of the Bureau of Land Management from 10 May 1984 to 10 November 1984 and approved 23 September 1985, this corner was "determined at record bearing and dist. from the remains of the orig. bearing trees: A decayed and burnt hemlock stump, size indeterminate, bears N.60°E., 12 lks. dist., with no mks. visible. (and) A decayed and burnt cedar stump, size indeterminate, bears N.58°W., 34 lks. dist., with no mks. visible." The BLM field notes indicate that this corner was positioned in such a way that the closing corner common to sections 4 and 5, T51N, R33W is located easterly at record U.S. distance (14 lks.) and on the line connecting this standard corner with the nearest recovered and accepted standard corner to the east. That corner being the corner common to sections 33 and 34, T52N, R33W. The BLM did not remonument the corner nor did they note any new bearing trees.

SURVEY &
REMONUMENTATION

MAY 05 1997

COMMISSION