

SURVEY & REMONUMENTATION

FEB 23 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**

<u>Baraga</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>33W</u>	<u>E-1*</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 30TH DAY OF DECEMBER A.D. 1997 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGE 797

Helda Bishop

REGISTER OF DEEDS FOR BARAGA COUNTY
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael Mileski, in a field survey on 20 November, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-1; North One-quarter Corner Section 4, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1845 and monumented with a wood post witnessed by a Tamarack 6 N06°W 131 lks. and a Tamarack 3 S78°W 70 lks.

No subsequent record evidence bearing upon the location of this corner was found. **APPROVED LAND CORNER P.A. 345 OF 1990 Baraga County**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-1; North One-quarter Corner Section 4, T52N, R33W;

This corner was considered lost and reestablished on line at the proportionate distance between the N¼ corner of section 5 and the NE corner of section 4. The N¼ corner of section 5 is an original U.S. corner. The NE corner of section 4 is probably an original U.S. corner. This corner position falls approximately in the center of an east-west, 30' wide ditch. Two witness corners were set, both at right angles to the section line using the one-quarter corner as a vertex. One witness corner lies northerly at a distance of 35.00 feet from the one-quarter corner. The other witness corner lies southerly, also at a distance of 35.00 feet from the one-quarter corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-1; North One-quarter Corner Section 4, T52N, R33W;

Both of the witness corners described in Part B were monumented with a 1" (I.D.) x 36" galvanized iron pipe and cap stamped as to location. There are no available accessories for either witness corner.

North Witness Corner

6' Steel fence post w/ yellow sign South 7.0'

Physical centerline of an east-west, 15' wide, gravel road.
North 28.6'

South Witness Corner

6' Steel fence post w/ yellow sign North 7.0'

Both witness corners were set 6" below ground.



*This corner is also F-13 of T53N, R33W.

LIBER 4 PAGE 797

igned by *Michael Mileski*

19 97