

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

RECEIVED FOR RECORD THIS 14TH DAY OF
 JANUARY A. D. 1999 AT 10:30 A. M. AND
 RECORDED IN LIBER 5 OF LAND CORNER
 RECORDATION RECORDS ON PAGE 27.

Relda Bishop

BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Located In: Baraga (County) Corner Code # F-9

1. Public Land Survey T 52N R 33W F-9
 T ___ R ___
 T ___ R ___
 T ___ R ___

2. Property Controlling S ___ T ___ R ___
 in Section S ___ T ___ R ___

3. Miscellaneous S ___ T ___ R ___
 Property in Sec. S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Michael Mileski, in a field survey on September, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
F-9; One-quarter Corner common to Sections 21 and 28, T52N, R33W;
 Originally established during U.S. Survey conducted by William Burt, D.S. in 1849 and monumented with a cedar post witnessed by a Yellow Birch 7 N12°E 8 lks. and a Fir 6 S50°W 6 lks. Found no subsequent record evidence.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
F-9; One-quarter Corner common to Sections 21 and 28, T52N, R33W;
 Found no monument at this corner. Reestablished the corner at the point of intersection of a line originating at the NE corner of section 28 and passing through an iron rod at the E1/16 corner with the northerly extension of a very old fence to the south. This corner position falls in the physical centerline of an east-west, graded gravel road (Helberg Road).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
F-9; One-quarter Corner common to Sections 21 and 28, T52N, R33W;
 Set a 1" (I.D.) x 36" galvanized iron pipe with cap 12" below the road surface.

Set 7" spike	SW/side	11" Cedar	N20°E	35.72'
Set 7" spike	SW/side	6" White Spruce	S39°E	65.09'
Set 7" spike	W/side	14" Cedar	S10°W	48.77'
Set 7" spike	SW/side	8" Cedar	N34°W	42.08'
		6' Steel fence post w/ yellow sign	North	27.0'

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9						●							
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													



Signed by *Michael Mileski*
 Surveyor's Michigan License No. 39091

Date 28 Dec 1998

APPROVED LAND CORNER
 P.A. 345 OF 1990
 Baraga County
 12-17-98