

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Baraga
(County)

Located in:

Corner Code #

- | | | |
|------------------------------------|---------------------------|-------|
| 1. Public Land Survey | T <u>52N</u> R <u>33W</u> | F-11 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

RECEIVED FOR RECORD THIS 14TH DAY OF
 JANUARY A. D. 1999 AT 10:30 A. M. A.
 RECORDED IN LIBER 5 OF LAND CORNER
 RECORDATION RECORDS ON PAGE 28.

Felda Bishop

BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael Mileski, in a field survey on October, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-11; One-quarter Corner common to Sections 28 and 33, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1849 and monumented with a cedar post witnessed by a Hemlock 14 N20°E 24 lks. and a Hemlock 15 S85°W 20 lks.

On page 4 of the Baraga Township Highways Journal, the centerline of the Keweenaw Bay and Otter Lake Road (presently known as Sturgeon Road) was described as passing through this corner (entry dated 30 August 1900). On page 11, John Rasmussen, County Surveyor, indicates that Simula Road (presently known as Bucher Road) begins at the N ¼ corner of section 33 and proceeds south 1320 feet to the 1/16 post. This entry was probably written in 1918. This corner was reestablished in approximately 1993 by Keith Sackett, PS #19006 at the physical intersection of Sturgeon Road and Bucher Road during the course of a survey conducted in the SE ¼ of section 28. Mr. Sackett had set a survey nail at the 1/16 corner position to the east. He also monumented the SE 1/16 corner of section 28.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3			2
3													
4	7			8			9			10			11
5													
6	18			17			16			15			14
7													
8	19			20			21			22			23
9													
10	30			29			28			27			26
11													
12	31			32			33			34			35
13													

B Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-11; One-quarter Corner common to Sections 28 and 33, T52N, R33W;

Found a survey (p-k) nail at the physical intersection of Sturgeon Road and Bucher Road as set by Mr. Sackett. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-11; One-quarter Corner common to Sections 28 and 33, T52N, R33W;

Replaced found monument with a 1" (I.D.) x 36" galvanized iron pipe with cap. This monument was set 9" below the asphalt. The 8 inch diameter asphalt opening was filled with 6 inches of MDOT-furnished CP-7 material. A 7" spike was set at the surface directly above the iron pipe monument.

Set 7" spike	SE/side	17" Spruce	N37°E	53.44'
Set 7" spike	NE/side	15" Spruce	S39°E	71.23'
Set 7" spike	NW/side	8" Willow	S40°W	81.63'
Set 7" spike	SW/side	14" Spruce	N61°W	80.34'
		7' Steel fence post w/ yellow sign	North	27.0'

All of the above new bearing trees were marked with upper and lower blazes. The lower blaze was scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.



Signed by _____
 Surveyor's Michigan License No. 39091

Date 28 Dec 1998

APPROVED LAND CORNER
 P.A. 345 OF 1990
 Baraga County

12-17-98
