

**SURVEY &  
MONUMENTATION**

MAY 05 1997

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in **COMMISSION**

<u>Baraga</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>33W</u>	F-13
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECEIVED FOR RECORD THIS 20TH DAY OF DECEMBER, 1996 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGES 709-710.

*Fields McAnty*  
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Michael Mileski, in a field survey on November, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

F-13; South One-quarter Corner Section 33, T52N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-13; South One-quarter Corner Section 33, T52N, R33W;

This corner was reestablished midway on line between the SE corner of section 33 and the SW corner of section 33. This corner so established falls 3 feet north of the physical centerline of Bear Town Road which at this point is a 15 foot wide gravel road bearing east and west. A fence to the north is located east a distance of 27 feet.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13; South One-quarter Corner Section 33, T52N, R33W;

Set a 1" (I.D.) x 36" galvanized iron pipe with a 2" aluminum cap stamped as to location 12" below the road surface.

Set 7" spike	W/side	14" Sugar Maple	North	42.37'
Set 7" spike	NW/side	16" Sugar Maple	N27°E	63.43'
Set 7" spike	NE/side	11" Sugar Maple	S55°E	62.54'
Set 7" spike	NW/side	12" Red Maple	S34°W	72.36'
		Location Post	North	18.5'

All of the above new bearing trees are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes as well as a band around the tree at the upper blaze are painted red.



Signed by *Michael Mileski*

Date 18 Dec 1996

Surveyor's Michigan License No. 39091

A. Description of original monument and accessories and/or subsequent restoration:

F-13; South One-quarter Corner Section 33, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Sugar	16	N45°E	3 lks.
and a			
Hemlock	7	N75°W	11 lks.

During the course of a survey conducted by Stephen Douglas of the Bureau of Land Management from 10 May 1984 to 10 November 1984 and approved 23 September 1985, this corner was considered lost and reestablished midway and on line between standard corners immediately to the east and west. The BLM field notes indicate that "From this point, the ¼ sec. cor. of secs. 4 and 33, erroneously reestablished using an improper controlling cor. by Marshall J. Hall, Junior Engineer, U.S. Indian Service, in 1935, bears S. 29°32.5' E., 0.034 chs. dist., determined at record bearing and dist.; from the remains of the 1935 bearing accessories."

The BLM did not monument the corner nor did they note any accessories.

SURVEY &  
REMONUMENTATION

MAY 05 1997

COMMISSION