

**SURVEY &
REMONUMENTATION**

FEB 23 1998

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in **SECTION**

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>R33W</u>	<u>G-1*</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECEIVED FOR RECORD THIS 30th
DAY OF DECEMBER A. D. 1997 A
10:30 A.M. AND RECORDED IN
LIBER 4 OF LAND CORNER
RECORDATION RECORDS ON PAGE
798-799.

Helda Bishop

BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael Mileski, in a field survey on 9 July, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-1; Section Corner common to Sections 3 and 4, T52N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-1; Section Corner common to Sections 3 and 4, T52N, R33W;

Found a 1" x 36" galvanized iron pipe with a Michigan Department of Conservation 4" aluminum cap as set by Keith Sackett, P.S. in 1977. Replaced the found monument with a 1" (I.D.) x 36" galvanized iron pipe and cap. Reset the DNR monument upside-down and along the west side of the new monument. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1; Section Corner common to Sections 3 and 4, T52N, R33W;

Set a 1" (I.D.) x 36" galvanized iron pipe with cap stamped as to location projecting 8" above ground.

- | | | | | | |
|------|--------------|---------|------------------------------------|-------|--------|
| i) | Set 7" spike | NW/side | 7" Tamarack | N33°E | 18.88' |
| ii) | Set 7" spike | N/side | 7" Tamarack | N88°E | 9.83' |
| iii) | Set 7" spike | SW/side | 9" Tamarack | S23°E | 17.00' |
| iv) | Set 7" spike | E/side | 8" Cedar | S02°W | 23.36' |
| v) | Set 7" spike | SE/side | 7" Spruce | S58°W | 18.58' |
| vi) | Set 7" spike | N/side | 8" Tamarack | N60°W | 17.09' |
| | | | 6" Steel fence post w/ yellow sign | North | 1.5' |

(i), (ii), and (iii) are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

(iv), (v) and (vi) are Mr. Sackett's new bearing trees and are further described in Part A. These new bearing trees were also painted red.

*This corner is also G-13 of T53N, R33W.

LIBER 4 PAGE 798

Signed by *Michael Mileski*
Surveyor's Michigan License No. 39091

Date 19 Dec 1997

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County

10-19-97
[Signature]



A. Description of original monument and accessories and/or subsequent restoration:

G-1; Section Corner common to Sections 3 and 4, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Tamarack 6 N56°W 35 lks.

and a

Tamarack 4 N29°E 53 lks.

During the subdivision of T52N, R33W, by William Burt, D.S. in 1849, this corner was further witnessed by a

Tamarack 5 S72°W 26 lks.

and a

Tamarack 3 S20°E 06 lks.

On 2 May 1977, Keith Sackett, P.S. #19006 of the Michigan Department of Natural Resources "found old post by P.A. Larsen". According to a Land Corner Recordation Certificate prepared by Mr. Sackett dated 3 August 1977 and recorded on 20 December 1977 in Volume 1 on page 481 of the Houghton County Land Corner Records, the wood post was replaced with a 1" (I.D.) x 36" iron pipe with 4" aluminum cap. The following accessories were noted:

Tamarack stub with P.A. Larsen marks N83°E 12.9'
Found on ground and in decay with scribing visible.
Measured N83°E 13.0'

6" Cedar S01°E 23.0'
Presently alive and 8" in diameter having partially healed upper and lower blazes.
No marks visible.

Set 7" spike E/side Measured S02°W 23.36'

6" Spruce S56°W 18.3'
Presently alive and 7" in diameter having partially healed upper and lower blazes with scribing visible.

Set 7" spike SE/side Measured S58°W 18.58'

6" Tamarack N60°W 16.9'
Presently alive and 8" in diameter having partially healed upper and lower blazes with scribing barely visible.

Set 7" spike N/side Measured N60°W 17.09'

SURVEY &
REMONUMENTATION

FEB 23 1998

SECTION