

MAR 30 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>33W</u>	<u>G-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 25th DAY
FEBRUARY A.D. 2000 AT 10:30 A.M.
AND RECORDED IN LIBER 5 OF LAND
CORNER RECORDATION RECORDS ON
PAGE 93 and 94.

Richard Bishop
BARAGA COUNTY REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Michael Mileski, in a field survey on July, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-2; One-quarter Corner common to Sections 3 and 4, T52N, R33W;
See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-2; One-quarter Corner common to Sections 3 and 4, T52N, R33W;
Reestablished corner midway and on line between the NE corner of section 4 and the SE corner of section 4. The original U.S. distance for this line is 80.00 chains. Assuming the section line bears north and south, the 1980 DNR witness corner is located 17.90 feet south and 1.12 feet east of this position. The east-west drainage ditch that Mr. Sackett refers to has been abandoned and is now dry. This position falls on the centerline of another drainage ditch extended to the east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-2; One-quarter Corner common to Sections 3 and 4, T52N, R33W;
Set a 1" (I.D.) x 36" galvanized iron pipe with cap 10 inches below ground.
1" dia. iron pipe S03°38'E 17.93' (1980 DNR witness corner)
There are no available accessories. This corner lies 33 feet east and 73 feet south of the centerline of a gravel access road.

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County
12-16-99
[Signature]



Signed by [Signature]
Surveyor's Michigan License No. 39091

Date 27 Dec 1999

MAR 30 2000

SECTION

A. Description of original monument and accessories and/or subsequent restoration:

G-2; One-quarter Corner common to Sections 3 and 4, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1849 and monumented with a tamarack post witnessed by a

Tamarack 4 N12°W 35 lks.

and a

Tamarack 6 S65°E 13 lks.

This corner is indicated on a section diagram drawn in a set of field notes taken by Fesing and Flynn dated 24 February 1919. No description of the monument or accessories is given. The distance to the NW corner of section 4 is given as 2641.4 feet. The distance to the SW corner of section 3 is also given as 2641.4 feet. The diagram indicates that the southwest 1/4 of section 3 was subdivided into 1/4 - 1/4 sections.

On 7 October 1980, Keith Sackett, PS #19006 reestablished this corner on line between government corners immediately to the north and south at a distance proportionate to the U.S. record. Mr. Sackett states "Set 1" I.D. x 32" iron pipe 18.10 ft. south of corner, 225 ft. West of center line railroad tracks. Corner falls in deep drainage ditch." No accessories are noted.

Refer to the Land Corner Recordation Certificate recorded by Mr. Sackett on 16 April 1982 in Liber 4, page 48, Baraga County Land Corner Records.