

MAR 30 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>52N</u> R <u>33W</u>	<u>G-3</u>	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____

RECEIVED FOR RECORD THIS 25th DAY  
FEBRUARY A.D. 2000 AT 10:30 A.M.  
AND RECORDED IN LIBER 5 OF LAND  
CORNER RECORDATION RECORDS ON  
PAGE 91 and 92.

*Nelda Bishop*

BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Michael Mileski, in a field survey on July, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-3; Section Corner common to Sections 3, 4, 9 and 10, T52N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-3; Section Corner common to Sections 3, 4, 9 and 10, T52N, R33W;

Found MDNR monument as described in Part A. Corner is located approximately 60 feet east of the centerline of a north-south gravel access road. I did not remonument this corner. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-3; Section Corner common to Sections 3, 4, 9 and 10, T52N, R33W;

Found Michigan Department of Natural Resources 1" (I.D.) iron pipe with 4" aluminum cap as set in 1980.

i) Set 7" spike	SE/side	12" Black Spruce	N47°E	20.06'
ii) Set 7" spike	NE/side	15" Cedar	S45°E	15.19'
iii) Set 7" spike	NW/side	12" Aspen	S16°W	109.39'
		Centerline of top of 6" steel I-beam	N53°W	64.76'
		6' Steel fence post w/ yellow sign	North	2.0'

i) and ii) are MDNR new bearing trees and are further described in Part A.

iii) is a new bearing tree marked with upper and lower blazes. The lower blaze was scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Baraga County

12-16-99  
[Signature]



Signed by \_\_\_\_\_  
Surveyor's Michigan License No. 39091

Date 29 Dec 1999

MAR 30 2000

SECTION

A. Description of original monument and accessories and/or subsequent restoration:

G-3; Section Corner common to Sections 3, 4, 9 and 10, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1849 and monumented with a tamarack post witnessed by a

Tamarack 6 S49°E 22 lks.

and a

Tamarack 6 N63°W 5 lks.

On 6 October 1980, Keith Sackett, PS #19006 found "two very old post and stumps of original B.T.'s". Mr. Sackett remonumented this corner with a 1" (I.D.) x 32" iron pipe with 4" aluminum cap and noted the following accessories:

9" Tamarack N16°W 16.0'  
Recovered as a 12" diameter stump 2.5 feet in height with scribing visible.  
Measured N19°W 19.0' to center.

8" Spruce N47°E 19.5'  
Presently alive and 12" in diameter having partially healed upper and lower blazes with scribing visible. Reblazed upper and lower blazes. Both blazes and a band around the tree at the upper blaze were painted red.  
Set 7" spike SE/side Measured N47°E 20.06'

6" Cedar S46°E 14.5'  
Presently alive and 15" in diameter having no visible blazes. Added an upper and lower blaze. The lower blaze was scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.  
Set 7" spike NE/side Measured S45°E 15.19'

Refer to Land Corner Recordation Certificate filed by Mr. Sackett and recorded on 16 April 1982 in Liber 4, page 49, Baraga County Land Corner Records.