

MAR 30 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>33W</u>	<u>G-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 25th DAY
FEBRUARY A.D. 2000 AT 10:30 A.M.
AND RECORDED IN LIBER 5 OF LAND
CORNER RECORDATION RECORDS ON
PAGE 89 and 90.

Nelda Bishop

BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Michael Mileski, in a field survey on July, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	
1													
2		6		5		4		3		2		1	
3													
4		7		8		9	●	10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-4; One-quarter Corner common to Sections 9 and 10, T52N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-4; One-quarter Corner common to Sections 9 and 10, T52N, R33W;

Found a 1" x 12" steel drift pin 5.8 feet south of the physical centerline of Arnheim Road as set by Keith Sackett, PS in 1980. Accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-4; One-quarter Corner common to Sections 9 and 10, T52N, R33W;

Set 1"(I.D.) x 36" galvanized iron pipe and cap. This monument was set 12 inches below the asphalt. The eight inch diameter asphalt opening was filled with 6 inches of MDOT-furnished CP-7 material. A 7" spike was set at the surface directly above the iron pipe monument.

i) Set 7" spike	SE/side	Power Pole	N75°E	153.76'
ii) Set 7" spike	SW/side	15" Yellow Birch	S36°E	47.39'
iii) Set 7" spike	W/side	30" Yellow Birch	S10°E	75.93'
iv) Set 7" spike	SW/side	Power Pole	N79°W	156.73'
		6' Steel fence post w/ yellow sign	North	35.0'

i),ii) and iv) are MDNR accessories and are further described in Part A.

iii) is a new bearing tree and is marked with upper and lower blazes. The lower blaze was scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County

12-16-99
257



Signed by *Michael Mileski*

Date 27 Dec 1999

Surveyor's Michigan License No. 39091

MAR 30 2000

SECTION

A. Description of original monument and accessories and/or subsequent restoration:

G-4; One-quarter Corner common to Sections 9 and 10, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1849 and monumented with a cedar post witnessed by a

Tamarack 10 N40°E 45 lks.

and a

Tamarack 8 S64°W 22 lks.

A letter dated 17 June 1905 from Mr. E.W. MacPherran, land commissioner for the Duluth, South Shore & Atlantic Railway / Mineral Range Railroad Company to Mr. Fred W. Schwalm, Baraga Township Supervisor indicates that a road was to be centered on the east-west 1/4 line of both sections 8 and 9, T52N, R33W.

An undated entry on page 54 in the Baraga Township Highways Journal indicates that the Arnheim & Otter Lake Road is to run "commencing at a point where the Duluth South Shore and Atlantic RR intersects the quarter line of sec. Ten (10) in Township Fifty Two (52) Range Thirty Three (33) West then running west to a point Forty (40) rods west of the Sturgeon River".

According to a Land Corner Recordation Certificate dated 26 January 1982 and recorded on 16 April 1982 in Liber 4 on page 49, Baraga County Records, on 6 October 1980 Keith Sackett, PS #19006 reestablished this corner midway and on line between original corners immediately to the north and south. Mr. Sackett monumented this position with a 1" diameter steel drift pin and established the following accessories:

10" Yellow Birch S33°E 46.8'

Presently alive and 15" in diameter having partially healed upper and lower blazes.

A scribed "NBT" was added to the lower blaze and a 7" spike was set on the southwest side. Both blazes and a band around the tree at the upper blaze were painted red.

Measured S36°E 47.39'

Power Pole N79°E 153.80'

Recovered MDNR nail and tag on southeast side.

Set a 7" spike directly below the MDNR nail and tag.

Measured N75°E 153.76'

Power Pole N75°W 156.75'

Recovered MDNR nail and tag on southwest side.

Set a 7" spike directly below the MDNR nail and tag.

Measured N79°W 156.73'