

MAR 30 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION

Baraga (County) Located In: Corner Code #
1. Public Land Survey T 52N R 33W G-6
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

RECEIVED FOR RECORD THIS 25th DAY FEBRUARY A.D. 2000 AT 10:30 A.M. RECORDED IN LIBER 5 OF LAND CORNER RECORDATION RECORDS ON PAGE 68.

Relda Bishop
BARAGA COUNTY REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, Michael Mileski, in a field survey on July, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-6; One-quarter Corner common to Sections 15 and 16, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1849 and monumented with a cedar post witnessed by a Hemlock 18 S77°E 27 lks. and a Yellow Birch 6 N75°W 18 lks.

No evidence of subsequent restoration was found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-6; One-quarter Corner common to Sections 15 and 16, T52N, R33W;

Reestablished corner midway and on line between the NE corner of section 16 and the SE corner of section 16. The NE corner of section 16 is an original corner. An old scribed post was found at the SE corner of section 16 by Keith Sackett, PS #19006 of the Michigan Department of Natural Resources in 1977.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-6; One-quarter Corner common to Sections 15 and 16, T52N, R33W;

Set a 1" (I.D.) x 36" galvanized iron pipe with cap projecting six inches above ground.

Table with 5 columns: Description, Direction, Tree/Post, Bearing, Distance. Includes entries for 7" spikes and a 6' steel fence post.

All of the above new bearing trees were marked with upper and lower blazes. The lower blaze was scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

APPROVED LAND CORNER P.A. 345 OF 1990 Baraga County

12-16-99
[Signature]



Signed by [Signature]
Surveyor's Michigan License No. 39091

Date 27 Dec 1999