

MAR 30 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>33W</u>	<u>G-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 25th DAY
FEBRUARY A.D. 2000 AT 10:30 A.M.
AND RECORDED IN LIBER 5 OF LAND
CORNER RECORDATION RECORDS ON
PAGE 87 and 88.

Relda Bishop
BARAGA COUNTY REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Michael Mileski, in a field survey on July, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		6		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-7; Section Corner common to Sections 15, 16, 21 and 22, T52N, R33W;
See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-7; Section Corner common to Sections 15, 16, 21 and 22, T52N, R33W;
The DNR monument set in 1977 has been destroyed. Remonumented this corner from both of the 1977 DNR bearing trees. The condition of each is as described in Part A. There are fence lines to the north, east and west. This corner is 9 feet west of the centerline of a north-south, 10-foot wide trail road. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-7; Section Corner common to Sections 15, 16, 21 and 22, T52N, R33W;

Set a 1" (I.D.) x 36" galvanized iron pipe with cap flush with the ground.

Set 7" spike	SE/side	11" White Spruce	N46°E	39.28'
Set 7" spike	SE/side	15" Red Pine	S37°W	43.92'
Set 7" spike	N/side	8" White Spruce	S85°W	31.47'
Set 7" spike	NE/side	8" Balsam	N40°W	12.84'
		6' Steel fence post w/ yellow sign	West	2.0'

All of the above new bearing trees are marked with upper and lower blazes. The lower blaze was scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County

12-16-99
[Signature]



Signed by [Signature]
Surveyor's Michigan License No. 39091

Date 27 Dec 1999

MAR 30 2000

SECTION

A. Description of original monument and accessories and/or subsequent restoration:

G-7; Section Corner common to Sections 15, 16, 21 and 22, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1849 and monumented with a cedar post witnessed by a

Cedar 15 N77°W 15 lks.

and a

Yellow Birch 15 S32°E 21 lks.

On 13 April 1977, Keith Sackett, PS #19006 found an "old scribed post in line with fences north, east and west and roads south". Mr. Sackett remonumented this corner with a 1" x 36" iron pipe with 4" aluminum cap and noted the following accessories:

4" Maple S66°E 30.7'
Presently alive and 8" in diameter having healed upper and lower blazes.
Measured S69°E 30.5' to face.

13" Maple N01°E 22.5'
Presently alive and 17" in diameter having healed upper and lower blazes.
Measured N03°W 22.3' to face.

An unrecorded land corner recordation certificate prepared by Mr. Sackett is on file at the DNR office in Baraga.