

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Baraga (County) Located In: Corner Code #
1. Public Land Survey T 52N R 33W G-9
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

RECEIVED FOR RECORD THIS 14TH DAY OF JANUARY A. D. 1999 AT 10:30 A. M. AND RECORDED IN LIBER 5 OF LAND CORNER RECORDATION RECORDS ON PAGE 29.

Relda Bishop
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, Michael Mileski, in a field survey on September, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-9; Section Corner common to Sections 21, 22, 27 and 28, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1849 and monumented with a cedar post witnessed by a Yellow Birch 12 N60°E 22 lks. and a Yellow Birch 10 S81°W 32 lks. On page 66 of the Baraga Township Highways Journal, John Markle, County Surveyor, indicates that a county road is to begin at the NW corner of section 27 and run east along the section line to the L'Anse and State line road (entry dated 16 August 1909). This corner is indicated on the plat of "Bayshore Acres" recorded 18 August 1967. Bayshore Acres was surveyed by Helmuth Steinhilb, PS #8896. Mr. Steinhilb indicates in the description that the corner is an "iron pin embedded in a county road". No accessories are noted.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-9; Section Corner common to Sections 21, 22, 27 and 28, T52N, R33W;

Found a 1 1/2" square head bolt pressed into a 1 1/4" (I.D.) x 14" iron pipe in the physical centerline of an east-west, graded gravel road (Helberg Road). This monument was found 8 inches below the road surface. Strongly occupied fences run to the north and to the south. This monument is consistent with the plat of "Bayshore Acres". Accepted as the best available evidence as to the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-9; Section Corner common to Sections 21, 22, 27 and 28, T52N, R33W;

Replaced found monument with a 1" x 36" galvanized iron pipe with cap stamped as to location. This monument was set 12 inches below the road surface.

APPROVED CORNER
P.A. 1990
Baraga County

12-17-98
[Signature]

Table with 5 columns: Monument Description, Bearing, Distance, etc.
Set 7" spike SE/side 7" White Spruce N51°E 84.21'
Set 7" spike SW/side 19" White Pine S37°E 87.43'
Set 7" spike SE/side 11" White Spruce S44°W 32.09'
Set 7" spike SW/side 7" White Spruce N40°W 52.36'
6' Steel fence post w/ yellow sign South 33.0'

All of the above new bearing trees were marked with upper and lower blazes. The lower blaze was scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.



Signed by [Signature]

Date 20 Dec 1998

LIBER 5

PAGE 29