

SENIOR

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Baraga (County) Located In: Corner Code #
1. Public Land Survey T 52N R 33W G-10
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

RECEIVED FOR RECORD THIS 14TH DAY OF JANUARY A. D. 1999 AT 10:30 A. M AND RECORDED IN LIBER 5 OF LAND CORNER RECORDATION RECORDS ON PAGE 30.

Relda Bishop
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Table with 13 columns (A-M) and 13 rows (1-13) for recording corners. A dot is marked in row 10, column G.

I, Michael Mileski, in a field survey on October, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-10; One-quarter Corner common to Sections 27 and 28, T52N, R33W;
Originally established during U.S. Survey conducted by William Burt, D.S. in 1849 and monumented with a spruce post witnessed by a Sugar 10 N49°W 27 lks. and a Yellow Birch 15 S39°E 34 lks.

No subsequent record evidence was found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-10; One-quarter Corner common to Sections 27 and 28, T52N, R33W;
This corner was considered lost. The corner was reestablished midway and on line between section corners immediately to the north and south. From this position, an old, mostly fallen fence runs to the east and to the west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-10; One-quarter Corner common to Sections 27 and 28, T52N, R33W;
Set a 1" (I.D.) x 36" galvanized iron pipe with cap stamped as to location projecting 6" above the ground.
Set 7" spike NW/side 8" Aspen N51°E 32.97'
Set 7" spike S/side 7" Aspen N77°E 31.65'
Set 7" spike N/side 17" Spruce S81°W 28.52'
NW Cor. Hse. S46°E 108.39'
7' Steel fence post w/ yellow sign North 1.5'

All of the above new bearing trees were marked with upper and lower blazes. The lower blaze was scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.



Signed by [Signature]
Surveyor's Michigan License No. 39091

Date 28 Dec 1998

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

LIBER 5 PAGE 30

REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT. 1988