

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

SECTION

RECEIVED FOR RECORD THIS 14TH DAY
 JANUARY A. D. 1999 AT 10:30 A. M.
 AND RECORDED IN LIBER 5 OF LAND
 CORNER RECORDATION RECORDS ON PAGE
 31.

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>33W</u>	<u>G-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Relda Bishop
 BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Michael Mileski, in a field survey on September, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-11; Section Corner common to Sections 27, 28, 33 and 34, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1849 and monumented with a cedar post witnessed by a Yellow Birch 8 N05°W 14 lks. and a Maple 10 S65°E 7 lks. This corner is indicated on highway alignment maps of old US-41, however, no description of the monument or accessories is given. This corner is also indicated on a survey conducted by Edward Charles, PS #12580 dated 1 December 1960. No description of the monument or accessories is given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-11; Section Corner common to Sections 27, 28, 33 and 34, T52N, R33W;

Found a 1" diameter hexagonal iron rod 22 inches in length 12 inches below the asphalt road surface. This monument is 6 feet south of the physical centerline of Sturgeon Road and 5.7 feet west of the physical centerline of old US-41. Accepted as the best available evidence as to the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-11; Section Corner common to Sections 27, 28, 33 and 34, T52N, R33W;

Replaced found monument with a 1" x 36" galvanized iron pipe with cap. This monument was set 12 inches below the asphalt. The 8 inch diameter asphalt opening was filled with 6 inches of MDOT-furnished CP-7 material. A 7" spike was set at the surface directly above the iron pipe monument.

Set 7" spike	SE/side	Power Pole	N49°E	49.31'
Set 7" spike	SW/side	Power Pole	S18°E	112.87'
Set 7" spike	E/side	6" Balsam	S15°W	84.96'
Set 7" spike	SE/side	7" Balsam	S35°W	89.53'
		7' Steel fence post w/ yellow sign	N45°W	50.0'

Both of the power poles were marked with a vertical red paint stripe. The new bearing trees were marked with upper and lower blazes. The lower blaze was scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.



APPROVED LAND CORNER
 P.A. 345 OF 1990
 Baraga County

Signed by *Michael Mileski*

12-17-98
244

Date 28 Dec 1998

Surveyor's Michigan License No. 39091

LIBER 5

PAGE 31