

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Baraga County

<u>Baraga</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>33W</u>	<u>G-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 14TH DAY OF JANUARY A. D. 1999 AT 10:30 A. AND RECORDED IN LIBER 5 OF LAND CORNER RECORDATION RECORDS ON PAGE 32.

Helda Bishop
 BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3		2		1	
3													
4	7		8			9		10		11		12	
5													
6	18		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33	●	34		35		36	
13													

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Michael Mileski, in a field survey on October, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-12; One-quarter Corner common to Sections 33 and 34, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1849 and monumented with a cedar post witnessed by a Yellow Birch 8 N05°W 14 lks. and a Maple 10 S65°E 7 lks.

This corner is indicated as the point of beginning of the recorded plat of "The Town of Keweenaw Bay". This plat was recorded on 15 September 1900. No description of the monument or accessories is given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-12; One-quarter Corner common to Sections 33 and 34, T52N, R33W;

Found a 1" x 21" square iron rod sharpened at one end at the base of a cedar fence post. Fences run to the north, south and west. This monument fits well with the south line of the plat of Keweenaw Bay. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-12; One-quarter Corner common to Sections 33 and 34, T52N, R33W;

Replaced found monument with a 1" (I.D.) x 36" galvanized iron pipe with cap stamped as to location and flush with the ground.

Set 7" spike	W/side	7" Sugar	N09°E	36.14'
Set 7" spike	SW/side	11" Sugar	N36°E	90.63'
Set 7" spike	E/side	11" White Pine	S10°W	85.05'
Set 7" spike	SE/side	12" White Pine	S53°W	90.77'
		6' Steel fence post w/ yellow sign	East	0.5'

All of the above new bearing trees were marked with upper and lower blazes. The lower blaze was scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

APPROVED AND CORNER:
 P.A. 74 OF 1970
 Baraga County
12-17-98
[Signature]



Signed by *[Signature]*
 Surveyor's Michigan License No. 39091

Date 28 Dec 1998