

**SURVEY &
REMONUMENTATION**

MAY 05 1997

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in **COMMISSION**

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>33W</u>	<u>G-13</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECEIVED FOR RECORD THIS 3RD DAY OF JANUARY, 1997 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGES 750-751.

Richard McAntyre
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael Mileski, in a field survey on December, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-13; Section Corner common to Sections 33 and 34, T52N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-13; Section Corner common to Sections 33 and 34, T52N, R33W;

Found a 2" x 24" iron pipe 6 inches below the road surface. This monument is located at the north edge of Bear Town Road 15 feet east of the centerline of a railroad. Replaced found iron pipe with a 1" (I.D.) x 36" galvanized iron pipe and cap. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13; Section Corner common to Sections 33 and 34, T52N, R33W;

Set a 1" (I.D.) x 36" galvanized iron pipe with a 2" aluminum cap stamped as to location 6 inches below the road surface.

i)	Set 7" spike	W/side	Power Pole	N32°E	28.66'
ii)	Set 7" spike	NE/side	7" Sugar Maple	S31°E	122.10'
iii)			NE Cor. RR sign	S11°W	19.88'
iv)	Set 7" spike	N/side	12" Red Maple	N81°W	90.22'
v)			C.C. Sec. 3 and 4	West	15.27'
vi)			Location Post	North	20.0'



(ii) and (iv) are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes as well as a band around the tree at the upper blaze are painted red.

(v) The closing corner of sections 3 and 4, T51N, R33W is monumented with a 1" (I.D.) x 36" galvanized iron pipe and cap.

Signed by *Michael Mileski*
Surveyor's Michigan License No. 39091

Date 5 Dec 1996
LIBER 4 PAGE 750

A. Description of original monument and accessories and/or subsequent restoration:

G-13; Section Corner common to Sections 33 and 34, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Sugar 8 N77°E 50 lks.

Fir 8 N40°W 33 lks.

During the course of a survey conducted by Stephen Douglas of the Bureau of Land Management from 10 May 1984 to 10 November 1984 and approved 23 September 1985, a 2" diameter iron pipe as set by Marshall J. Hall, Junior Engineer, U.S. Indian Service, in 1935 was recovered. The BLM field notes state that

" The field notes of the 1935 Marshall J. Hall survey, indicate that this position is the cor. common to secs. 3, 4, 33, and 34. However, the orig. record indicates two distinct cor. positions, the cor. of secs. 33 and 34, and the closing cor. of secs. 3 and 4, which are 23 lks. apart. A retracement of the line bet. secs. 33 and 34, T. 52N, R. 33W., and a retracement of the 1882 survey of the Duluth, Southshore and Atlantic R.R. confirmed the position to be the cor. of secs. 33 and 34, and not the closing cor. of secs. 3 and 4."

The BLM did not remonument the corner. The following ties to local bearing accessories were noted:

Maple 8 N60°E 117 lks. (77.22')
Gone.

Maple 6 S40°E 119½ lks. (78.87')
Gone.

RR sign post S10°W 30 lks. (19.80')
Measured S11°W 19.88' to NE corner.

Telephone Pole N20°W 105 lks. (69.30')
Gone.

This monument was erroneously recorded as the closing corner common to sections 3 and 4, T51N, R33W, in 1984. See LCRC, Liber 4, page 65, Baraga County Land Corner Records.

SURVEY &
REMONUMENTATION

MAY 05 1997

COMMISSION