

**SURVEY &  
REMONUMENTATION**

**FEB 23 1998**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in **SECTION**

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>33W</u>	<u>H-1*</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 30TH  
DAY OF DECEMBER A. D. 1997 AT  
10:30 A.M. AND RECORDED IN  
LIBER 4 OF LAND CORNER  
RECORDATION RECORDS ON PAGE  
800

*Helda Bishop*  
BARAGA COUNTY REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Michael Mileski, in a field survey on 2 December, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-1; North One-quarter Corner Section 3, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1845 and monumented with a wood post witnessed by a  
Yellow Birch 9 N80°W 20 lks.  
and a  
Yellow Birch 20 N20°E 42 lks.

No subsequent record evidence bearing upon the location of this corner was found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-1; North One-quarter Corner Section 3, T52N, R33W;

This corner was considered lost and reestablished midway and on line between the northwest corner of section 3 and the north one-quarter corner of section 2. The northwest corner of section 3 is a probable original U.S. corner. The north one-quarter corner of section 2 is an old fence corner monumented by Edward Charles, P.S. in 1969.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-1; North One-quarter Corner Section 3, T52N, R33W;

Set a 1" (I.D.) x 36" galvanized iron pipe and cap stamped as to location projecting 6" above ground.

Set 7" spike	SE/side	13" Red Maple	N29°E	3.09'
Set 7" spike	N/side	14" Cedar	S89°E	34.15'
Set 7" spike	NE/side	8" Sugar Maple	S35°E	31.17'
Set 7" spike	W/side	13" Sugar Maple	S02°E	45.89'
Set 7" spike	NE/side	12" Cedar	S87°W	0.94'
Set 7" spike	W/side	15" Sugar Maple	N11°W	34.09'
		6' Steel fence post w/ yellow sign	South	1.5'

All of the above new bearing trees are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

\*This corner is also H-13 of T53N, R33W.

LIBER 4 PAGE 800

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Baraga County

12-9-97  
*[Signature]*



Signed by *[Signature]*

Date 12 23 1997