

MAR 30 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| | | |
|---------------------------------------|---------------------------|---------------|
| <u>Baraga</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>52N</u> R <u>33W</u> | <u>H-5</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

RECEIVED FOR RECORD THIS 25th DAY
FEBRUARY A.D. 2000 AT 10:30 A.M.
AND RECORDED IN LIBER 5 OF LAND
CORNER RECORDATION RECORDS ON
PAGE 85 and 86.

Helda Bishop

BARAGA COUNTY REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Michael Mileski, in a field survey on July, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-5; One-quarter Corner common to Sections 10 and 15, T52N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-5; One-quarter Corner common to Sections 10 and 15, T52N, R33W;

Found a 4" diameter iron pipe 10" in length as noted by the Michigan Department of State Highways in 1968. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-5; One-quarter Corner common to Sections 10 and 15, T52N, R33W;

Set a 1" (I.D.) x 30" galvanized iron pipe with cap projecting 3 inches above ground.

| | | | | | |
|--------------|--------|------------------------------------|-------|--------|-------------------|
| Set 7" spike | W/side | 15" Cedar | N14°E | 32.22' | |
| Set 7" spike | S/side | 11" Cedar | S70°E | 18.60' | |
| Set 7" spike | E/side | 10" Cedar | S21°W | 36.52' | |
| Set 7" spike | N/side | 8" Balsam | N87°E | 5.99' | (R. Crampton NBT) |
| | | 6' Steel fence post w/ yellow sign | South | 2.0' | |

All of the above new bearing trees were marked with upper and lower blazes. The lower blaze was scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County

12-16-99
764



Signed by [Signature]
Surveyor's Michigan License No. 39091

Date 27 Dec 1999

MAR 30 2000

SECTION

A. Description of original monument and accessories and/or subsequent restoration:

H-5; One-quarter Corner common to Sections 10 and 15, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1849 and monumented with a cedar post witnessed by a

Cedar 8 N57°E 14 lks.

and a

Hemlock 10 S41°E 36 lks.

According to the Duluth, South Shore & Atlantic Railway plans, this corner is located 749 feet east of the centerline of the railroad.

This corner is indicated on a section diagram drawn in a set of field notes taken by Fesing and Flynn dated 24 February 1919. No description of the monument or accessories is given. The distance to the SE corner of section 10 is given as 2613 feet and the distance to the SW corner of section 10 is given as 2635.80 feet.

On the Michigan State Highway Department plans for Federal Aid Project No. 3 Sec. A-2 (File no. R-28-A-2B) approved 26 December 1935, this corner is shown as being monumented by a cedar stake which lies 2219.16 feet west of the centerline of U.S. Highway 41. No accessories are noted. The distance to the SE corner of section 10 is given as 2667.96 feet.

On the Michigan Department of State Highways plans for State Projects F07013-004 and Ms07012-006 approved 8 February 1968, this corner is shown as being monumented by a 4" diameter iron well casing which lies 2220.07 feet west of the centerline of U.S. Highway 41. The distance to the SE corner of section 10 is given as 2667.84 feet. The following accessories are noted:

| | | |
|-----------|-------|--------|
| 8" Cedar | S55°W | 31.22' |
| 8" Birch | S80°E | 17.47' |
| 3" Balsam | N25°W | 19.81' |

A mortgage report prepared by Robert Crampton, PS #24591 dated 26 September 1997 indicates a 4" diameter iron pipe as monumenting the corner. Mr. Crampton notes the following accessories:

| | | |
|---|-------|--------|
| 11" Maple | N22°W | 22.40' |
| Found an alive 12" diameter red maple having a nail and tag in a partially healed face blaze. | | |
| Measured | N27°W | 22.44' |

| | | |
|---|-------|-------|
| 6" Balsam | S81°E | 5.78' |
| Found an alive 8" diameter balsam having a nail and tag in a partially healed face blaze. | | |
| Measured | N87°E | 5.79' |

| | | |
|---|-------|--------|
| 3" Balsam | S25°E | 10.67' |
| Found an alive 4" diameter balsam having a nail and tag in a partially healed face blaze. | | |
| Measured | S32°E | 10.66' |

| | | |
|---|-------|-------|
| 3" Balsam | S83°W | 6.36' |
| Found an alive 4" diameter balsam having a nail and tag in a partially healed face blaze. | | |
| Measured | S79°W | 6.30' |