

**SURVEY &
REMONUMENTATION**

FEB 23 1998

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

SECTION

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>R33W</u>	<u>I-1*</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 30TH
DAY OF DECEMBER A.D. 1997 AT
10:30 A.M. AND RECORDED IN
LIBER 4 OF LAND CORNER
RECORDATION RECORDS ON PAGE
801

Helda Bishop

BARAGA COUNTY REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael Mileski, in a field survey on 2 December, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-1; Section Corner common to Sections 2 and 3, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1845 and monumented with a wood post witnessed by a Yellow Birch 14 N81°W 20 lks. and a Sugar 15 N61°E 43 lks.

During the subdivision of T52N, R33W by William Burt, D.S. in 1849, this corner was further witnessed by a Yellow Birch 8 S55°E 12 lks. and a Maple 10 S39°W 12 lks.

An undated map of T53N, R33W prepared by persons unknown indicates the corner as being monumented by a "cedar post". Notations on this map indicate that it may have been prepared sometime after 1914.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-1; Section Corner common to Sections 2 and 3, T52N, R33W;

This corner was considered lost and reestablished on line at the proportionate distance between the northwest corner of section 3 and the north one-quarter corner of section 2. The northwest corner of section 3 is a probable U.S. corner. The north one-quarter corner of section 2 is an old fence corner monumented by Edward Charles, P.S. in 1969.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-1; Section Corner common to Sections 2 and 3, T52N, R33W;

Set a 1" (I.D.) x 36" galvanized iron pipe and cap stamped as to location projecting 6" above ground.

Set 7" spike	E/side	12" Red Maple	N22°E	49.32'
Set 7" spike	S/side	15" Sugar Maple	N89°E	51.96'
Set 7" spike	NE/side	16" Sugar Maple	S39°E	15.91'
Set 7" spike	W/side	13" Yellow Birch	S23°E	30.27'
Set 7" spike	N/side	5" Sugar Maple	N84°W	14.86'
		6' Steel fence post w/ yellow sign	South	3'

All of the above new bearing trees are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

*This corner is also I-13 of T53N, R33W.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3					2			1
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County

10-9-97
[Signature]



LIBER 4 PAGE 801