

MAR 30 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>33W</u>	<u>I-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 25th DAY
FEBRUARY A.D. 2000 AT 10:30 A.M.
AND RECORDED IN LIBER 5 OF LAND
CORNER RECORDATION RECORDS ON
PAGE 81 and 82.

Nelda Bishop

BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Michael Mileski, in a field survey on July, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-2; One-quarter Corner common to Sections 2 and 3, T52N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-2; One-quarter Corner common to Sections 2 and 3, T52N, R33W;

Found 1/2" dia. iron rod and cap #37273 as set by Joseph Domitrovich, PS in 1999. This corner was verified by traverse to be at the proportioned position intended by Mr. Domitrovich. Accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-2; One-quarter Corner common to Sections 2 and 3, T52N, R33W;

Set a 1" (I.D.) x 36" galvanized iron pipe with cap over the found iron rod and cap. This monument projects six inches above the ground.

Set 7" spike	N/side	6" Balsam	N63°E	6.95'
Set 7" spike	NE/side	11" Red Maple	S55°E	12.20'
Set 7" spike	NW/side	7" Red Maple	S42°W	9.61'
Set 7" spike	W/side	11" Red Maple	N16°W	14.50'
		6' Steel fence post w/ yellow sign	West	1.0'

All of the above are Mr. Domitrovich's new bearing trees and are further described in Part A.

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County

12-16-99
[Signature]



Signed by [Signature]

Date 27 Dec 1999

Surveyor's Michigan License No. 39091

MAR 30 2000

SECTION

A. Description of original monument and accessories and/or subsequent restoration:

I-2; One-quarter Corner common to Sections 2 and 3, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1849 and monumented with a hemlock post witnessed by a

Maple 4 N30°W 34 lks.

and a

Hemlock 14 S40°E 31 lks.

On 30 June 1999, Joseph Domitrovich, PS #37273 reestablished this corner on line between government corners immediately to the north and south at a distance proportionate to the U.S. record. Mr. Domitrovich monumented this corner with a 1/2" diameter iron rod and cap #37273 and noted the following accessories:

6" Balsam N66°E 6.99'
 Presently alive and 6" in diameter. Reblazed upper and lower blazes and scribed the lower blaze "NBT". Set a 7" spike over a found nail and washer on the north side.
 Measured N63°E 6.95'

11" Soft Maple S54°E 12.24'
 Presently alive and 11" in diameter. Reblazed upper and lower blazes and scribed the lower blaze "NBT". Set a 7" spike over a found nail and washer on the northeast side.
 Measured S55°E 12.20'

7" Soft Maple S45°W 9.61'
 Presently alive and 7" in diameter. Reblazed upper and lower blazes and scribed the lower blaze "NBT". Set a 7" spike over a found nail and washer on the northwest side.
 Measured S42°W 9.61'

11" Soft Maple N12°W 14.45'
 Presently alive and 11" in diameter. Reblazed upper and lower blazes and scribed the lower blaze "NBT". Set a 7" spike over a found nail and washer on the west side.
 Measured N16°W 14.50'

On all of the above new bearing trees, both blazes and a band around the tree at the upper blaze were painted red.