

MAR 30 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>33W</u>	<u>I-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 25th DAY
FEBRUARY A.D. 2000 AT 10:30 A.M.
AND RECORDED IN LIBER 5 OF LAND
CORNER RECORDATION RECORDS ON
PAGE 79 and 80

Helda Bishop
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Michael Mileski, in a field survey on July, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-4; One-quarter Corner common to Sections 10 and 11, T52N, R33W;
See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-4; One-quarter Corner common to Sections 10 and 11, T52N, R33W;

Found a 1 1/4" x 38" iron pipe projecting 16" above ground. A 6" diameter cedar corner post with fences to the north and east bears S62°W a distance of 1.1 feet. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-4; One-quarter Corner common to Sections 10 and 11, T52N, R33W;

Set a 1" (I.D.) x 36" galvanized iron pipe with cap projecting 4" above ground.

- | | | | | |
|-------------------|---------|------------------------------------|-------|--------|
| i) Set 7" spike | SE/side | 8" Cedar | N61°E | 21.56' |
| ii) Set 7" spike | S/side | 10" Yellow Birch | S73°E | 24.23' |
| iii) Set 7" spike | N/side | 7" Balsam | N80°W | 22.18' |
| iv) Set 7" spike | W/side | 8" Red Maple | N23°W | 12.76' |
| v) | | 6' Steel fence post w/ yellow sign | South | 2.0' |

i) and iv) are Crampton new bearing trees and are further described in Part A.
ii) and iii) are new bearing trees marked with upper and lower blazes. The lower blaze was scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County

12-16-99
[Signature]



Signed by [Signature]
Surveyor's Michigan License No. 39091

Date 27 Dec 1999

MAR 30 2000

SECTION

A. Description of original monument and accessories and/or subsequent restoration:

I-4; One-quarter Corner common to Sections 10 and 11, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1849 and monumented with a cedar post witnessed by a

Hemlock 14 S77°E 28 lks.

and a

Yellow Birch 10 N67°W 33 lks.

This corner is indicated on a section diagram drawn in a set of field notes taken by Fesing and Flynn dated 24 February 1919. No description of the monument or accessories is given. The distance north to the NE corner of section 10 is noted as 2637.40 feet. The distance south to the SE corner of section 10 is noted as 2645.60 feet.

On the Michigan State Highway Department plans for Federal Aid Project No. 3 Sec. A-2 (File no. R-28-A-2B) approved 26 December 1935, this corner is shown as being 1464.3 feet north of the centerline of U.S. Highway 41. No description of the monument or accessories is given. The distance to the SE corner of section 10 is given as 2646.60 feet.

On the Michigan Department of State Highways plans for State Projects F07013-004 and Ms 07012-006 approved 8 February 1968, this corner is shown as being monumented by a 1½" diameter iron pipe which lies 1453.33 feet north of the centerline of U.S. Highway 41. The distance to the SE corner of section 10 is given as 2646.45 feet. The following accessories are noted:

6" Balsam	S80°E	8.36'
9" Poplar	S10°E	12.56'
8" Maple	N20°W	12.72'

On 4 March 1994, Robert Crampton, PS #24591 recovered a 1½" diameter iron pipe. Mr. Crampton noted the following new bearing trees:

6" Cedar N67°E 21.29'

Presently alive and 8" in diameter having a nail and tag set in a partially healed face blaze.

Set a 7" spike SE/side

Measured N61°E 21.56'

I added an upper and lower blaze. The lower blaze was scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

6" Balsam S57°E 30.82'

Presently alive and 7" in diameter having a nail and tag set in a partially healed face blaze.

Measured S62°E 30.81' to found nail and tag.

8" Balsam N66°W 37.88'

Presently alive and 10" in diameter having a nail and tag set in a partially healed face blaze.

Measured N71°W 37.86' to found nail and tag.

6" Maple N17°W 12.49'

Presently alive and 8" in diameter having a nail and tag set in a partially healed face blaze.

Set a 7" spike W/side

Measured N23°W 12.76'

I added an upper and lower blaze. The lower blaze was scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

Refer to Land Corner Recordation Certificate recorded in Liber 4, page 477.