

**SURVEY &
RECORDS ADMINISTRATION**

MAR 30 2000

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>33W</u>	<u>I-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 25th DAY
FEBRUARY A.D. 2000 AT 10:30 A.M.
and RECORDED IN LIBER 5 OF LAND
CORNER RECORDATION RECORDS ON
PAGE 77 and 78

Richard Bishop

BARAGA COUNTY REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Michael Mileski, in a field survey on July, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	I
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5								●				
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-5; Section Corner common to Sections 10, 11, 14 and 15, T52N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-5; Section Corner common to Sections 10, 11, 14 and 15, T52N, R33W;

Found a 1" x 53" steel drill rod projecting 10 inches above ground. This monument is located 448 feet east of the physical centerline of U.S. Highway 41 (recorded as 448.8' - MSHD 1935 and recorded as 447.77' - MDSH 1968) and 1195 feet south of the physical centerline of U.S. Highway 41 (recorded as 1182.3' - MSHD 1935 and recorded as 1193.12' - MDSH 1968). This monument is also located 946.48 feet west of the northwest corner of Lot 1 of the plat of Fremont Acres (recorded as 949.00'). Furthermore, the distances to the east 1/4 corner of section 10 and to the south 1/4 corner of section 10 are in close agreement with both the 1935 and 1968 U.S. Highway 41 plans. No accessories from 1919, 1935 or 1968 were positively identified. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-5; Section Corner common to Sections 10, 11, 14 and 15, T52N, R33W;

Set a 1" (I.D.) x 30" galvanized iron pipe and cap projecting 6" above ground.

i) Set 7" spike	W/side	14" Red Maple	N07°E	21.06'
ii) Set 7" spike	SE/side	15" Yellow Birch	N53°E	18.74'
iii) Set 7" spike	NE/side	15" Red Maple	S48°E	4.54'
iv) Set 7" spike	SE/side	17" Sugar Maple	S46°W	56.16'
		6' Steel fence post w/ yellow sign	North	2.0'

i), ii) and iii) are Crampton new bearing trees and are further described in Part A. iv) is a new bearing tree marked with upper and lower blazes. The lower blaze was scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County



Signed by *Michael Mileski* 12-16-99
Surveyor's Michigan License No. 39091

Date 27 Dec 1999

MAR 30 2000

SECTION

A. Description of original monument and accessories and/or subsequent restoration:

I-5; Section Corner common to Sections 10, 11, 14 and 15, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1849 and monumented with a cedar post witnessed by a

Yellow Birch 10 N56°W 42 lks.

and a

Hemlock 16 S75°E 27 lks.

This corner was reestablished by Fesing and Flynn on 24 February 1919 by "interpolation between S¼ of 10 and lakeshore east and ¼ 10 / 11 from the north". A section diagram drawn in the field notes of Fesing and Flynn shows this corner 2613 feet east of the S¼ corner of section 10 and 2645.6 feet south of the E¼ corner of section 10. The field notes indicate that a 4" square cedar post was set and witnessed by a 12" Birch N27°W 33½ lks. and a 8" Balsam S52°E 18½ lks.

On the Michigan State Highway Department plans for Federal Aid Project No. 3 Sec. A-2 (File no. R-28-A-2B) approved 26 December 1935, this corner is shown as being monumented by a cedar stake which lies 448.8 feet east and 1182.3 feet south of the centerline of U.S. Highway 41. No accessories are noted. The distance to the S¼ corner of section 10 is given as 2667.96 feet. The distance to the E¼ corner of section 10 is given as 2646.6 feet.

The plat of "Fremont Acres" recorded on 14 September 1964 in Volume 2 of Plats, page 72, Baraga County Records indicates this corner, but does not describe the monument nor does it describe any accessories. The plat which is bounded on the north by the north line of section 14 only indicates that the distance east from the section corner to the NW corner of the plat as being 878.3 feet. Fremont Acres was surveyed by Helmuth Steinhilb, PS #8896.

On the Michigan Department of State Highways plans for State Projects F07013-004 and Ms 07012-006 approved 8 February 1968, this corner is shown as being monumented by an axle shaft which lies 447.77 feet east and 1193.12 feet south of the centerline of U.S. Highway 41. The distance to the S¼ corner of section 10 is given as 2667.84 feet. The distance to the E¼ corner of section 10 is given as 2646.45 feet. The following accessories are noted:

8" Maple	S75°E	4.53'
4" Maple	S05°W	16.63'
6" Maple	N75°W	15.12'

A mortgage report prepared by Robert Crampton, PS #24591 dated 26 September 1997 notes that this corner is monumented by a drill rod. Mr. Crampton noted the following new bearing trees:

12" Maple	N13°E	20.41'
-----------	-------	--------

Presently alive and 14" in diameter having a nail and washer set in a partially healed face blaze.
Set a 7" spike W/side
Measured N07°E 21.06'
I added an upper and lower blaze. The lower blaze was scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

12" Yellow Birch	N60°E	18.14'
------------------	-------	--------

Presently alive and 15" in diameter having a nail and tag set in a partially healed face blaze.
Set a 7" spike SE/side
Measured N53°E 18.74'
I added an upper and lower blaze. The lower blaze was scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

12" Maple	S42°E	3.96'
-----------	-------	-------

Presently alive and 15" in diameter having a nail and tag set in a partially healed face blaze.
Set a 7" spike NE/side
Measured S48°E 4.54'
I added an upper and lower blaze. The lower blaze was scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

12" Maple	S69°W	31.02'
-----------	-------	--------

Found a 15" diameter maple stump 6" in height having no marks.
Measured S66°W 31.0' to face of stump.