

SURVEY & REMONUMENTATION

FEB 23 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>33W</u>	<u>J-1*</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 30TH DAY OF DECEMBER A.D. 1997 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGE 802-803

Nelda Bishop
BARAGA COUNTY REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Michael Mileski, in a field survey on 18 July, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-1; North One-quarter Corner Section 2, T52N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-1; North One-quarter Corner Section 2, T52N, R33W;

Found a 1" x 24" square iron rod sharpened at one end projecting 4" above ground. This monument is in an old fence line running east and west. An old fence also bears to the south. This corner was remonumented with a 1"(I.D.) x 36" galvanized iron pipe and cap. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-1; North One-quarter Corner Section 2, T52N, R33W;

Set a 1"(I.D.) x 36" galvanized iron pipe and cap stamped as to location projecting 6" above ground.

Set 7" spike	N/side	7" Hemlock	N58°E	13.66'
Set 7" spike	N/side	9" Hemlock	S83°E	18.32'
Set 7" spike	N/side	8" Hemlock	N84°W	12.66'
Set 7" spike	NE/side	14" Hemlock	N24°W	25.96'
		6' Steel fence post w/ yellow sign	North	10'

All of the above new bearing trees are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

*This corner is also J-13 of T53N, R33W.



LIBER 4 PAGE 802

Signed by *Michael Mileski*
 Surveyor's Michigan License No. 39091

Date 19 Dec 1997

SURVEY &
REMONUMENTATION

FEB 23 1998

SECTION

A. Description of original monument and accessories and/or subsequent restoration:

J-1; North One-quarter Corner Section 2, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Yellow Birch 7 N54°W 11 lks.

and a

Yellow Birch 18 N74°E 31 lks.

An undated map of T53N, R33W prepared by persons unknown indicates the corner as a cedar post set from original U.S. bearing trees. Notations on this map indicate that it may have been prepared sometime after 1914.

On 19 July 1969, Edward Charles, P.S. #12580 set an "iron pin in fence corner". Refer to Mr. Charles' field book number 7 on page 57. No accessories were noted.

On 20 June 1989, Robert Crampton, P.S. #24591 found and accepted a "1(in.) Square iron pin...at the intersection of two old fences East and South of the corner and Notes from Ed Charles". According to a Land Corner Recordation Certificate prepared by Mr. Crampton dated 24 August 1989 and recorded on 24 August 1989 in Volume 2 on page 633 of the Houghton County Land Corner Records, this corner was not remonumented. The following accessories were noted:

12" Maple	N14°E	16.89'		
Found cut stump of a 12" diameter red maple.				
Mr. Crampton's nail and tag found on the face.	Measured	N17°E	16.89'	
5" Maple	S78°E	11.12'		
Found an alive red maple 5" in diameter having a partially healed lower blaze.				
Mr. Crampton's nail and tag found on the face.	Measured	S74°E	11.15'	
12" Maple	S34°W	9.42'		
Found an alive red maple 12" in diameter having a partially healed lower blaze.				
Mr. Crampton's nail and tag found on the face.	Measured	S33°W	9.45'	
14" Maple	N41°W	4.0'		
Found cut stump of a 14" diameter red maple having a partially healed lower blaze.				
Mr. Crampton's nail and tag found on the face.	Measured	N45°W	4.03'	