

MAR 30 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>33W</u>	<u>J-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 25th DAY FEBRUARY A.D. 2000 AT 10:30 A.M. RECORDED IN LIBER 5 OF LAND CORNER RECORDATION RECORDS ON PAGE 75. AND 76.

*Helda Bishop*

BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Michael Mileski, in a field survey on July, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-3; One-quarter Corner common to Sections 2 and 11, T52N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-3; One-quarter Corner common to Sections 2 and 11, T52N, R33W;

Found a 3/4" diameter iron pipe with cap as set by Steven Hein, PS #32336 in 1995. This monument lies 148.15 feet west of a concrete monument representing the point of beginning of the plat of Des Rochers Brothers' Subdivision. This distance is recorded as 150 feet on the plat. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-3; One-quarter Corner common to Sections 2 and 11, T52N, R33W;

Set a 1" (I.D.) x 34" galvanized iron pipe and cap 8" below the road surface.

- |                   |         |                                    |       |        |
|-------------------|---------|------------------------------------|-------|--------|
| i) Set 7" spike   | W/side  | 4" Yellow Birch                    | N01°W | 55.92' |
| ii) Set 7" spike  | S/side  | 21" Red Maple                      | N87°E | 35.00' |
| iii) Set 7" spike | NE/side | 17" Cedar                          | S42°E | 22.20' |
| iv) Set 7" spike  | S/side  | 19" Red Maple                      | N75°W | 54.98' |
|                   |         | 6' Steel fence post w/ yellow sign | S54°E | 12.0'  |

i), ii), iii) and iv) are Hein new bearing trees and are further described in Part A.

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Baraga County

12-16-99  
[Signature]



Signed by [Signature]

Date 27 Dec 1999

Surveyor's Michigan License No. 39091

MAR 30 2000

SECTION

A. Description of original monument and accessories and/or subsequent restoration:

J-3; One-quarter Corner common to Sections 2 and 11, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1849 and monumented with a cedar post witnessed by a

Yellow Birch 14 N18°E 33 lks.

and a

Yellow Birch 12 S71°W 16 lks.

On the Michigan State Highway Department plans for Federal Aid Project No. 3 Sec. A-2 (File no. R-28-A-2B) approved 26 December 1935, this corner is shown as being monumented by a cedar stake which lies 1152.6 feet east of the centerline of U.S. Highway 41. No accessories are noted. The distance to the NW corner of section 11 is given as 2629.9 feet.

The plat of "Des Rochers Brothers' Subdivision" recorded on 7 October 1957 in Volume 2 of Plats, page 54, Baraga County Records indicates this corner, but does not describe the monument nor does it describe any accessories. The plat which is bounded on the south by the section line only indicates that the distance from the corner to the point of beginning of the plat is 150 feet. This plat was surveyed by Norman Thompson, PS #4348.

On the Michigan Department of State Highways plans for State Projects F07013-004 and Ms 07012-006 approved 8 February 1968, this corner is shown as being monumented by a 3/4" diameter iron pin which lies 1153.54 feet east of the centerline of U.S. Highway 41. The distance to the NW corner of section 11 is given as 2640.00 feet. The following accessories are noted:

14" Maple	N65°E	35.57'
7" Cedar	S45°E	22.88'
3" Cherry	N50°W	34.21'

On 8 August 1995, Steven Hein, PS #32336 found and accepted a "7/8" pin, badly bent, 4.5' easterly of Des Rochers Road". Mr. Hein replaced this monument with a 3/4" capped pipe and noted the following accessories:

4" Yellow Birch N02°E 55.82'  
Presently alive and 4" in diameter having a partially healed face blaze and a nail and tag set in a partially healed side blaze. I added an upper and lower blaze. The lower blaze was scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red. Set a 7" spike directly below the found nail and tag.  
Measured N01°W 55.92'

18" Red Maple East 35.06'  
Presently alive and 21" in diameter having a partially healed face blaze and a nail and tag set in a partially healed side blaze. I added an upper and lower blaze. The lower blaze was scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red. Set a 7" spike directly below the found nail and tag.  
Measured N87°E 35.00'

14" Cedar S38°E 22.29'  
Presently alive and 17" in diameter having a partially healed face blaze and a nail and tag set in a partially healed side blaze. I added an upper and lower blaze. The lower blaze was scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red. Set a 7" spike directly below the found nail and tag.  
Measured S42°E 22.20'

17" Red Maple N72°W 54.87'  
Presently alive and 19" in diameter having a partially healed face blaze and a nail and tag set in a partially healed side blaze. I added an upper and lower blaze. The lower blaze was scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red. Set a 7" spike directly below the found nail and tag.  
Measured N75°W 54.98'

Refer to Land Corner Recordation Certificate filed by Mr. Hein and recorded in Liber 4, page 622, Baraga County Land Corner Records.