

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Baraga  
 (County)

Located In:

Corner Code #

- 1. Public Land Survey      T 52N R 33W  
                                   T    R  
                                   T    R  
                                   T    R
- 2. Property Controlling    S    T    R  
   in Section                S    T    R
- 3. Miscellaneous         S    T    R  
   Property in Sec.        S    T    R

#17) East MC  
between B-9 and  
C-9

RECEIVED FOR RECORD THIS 14TH DAY OF  
 JANUARY A. D. 1999 AT 10:30 A. M.  
 AND RECORDED IN LIBER 5 OF LAND  
 CORNER RECORDATION RECORDS ON PAGE  
 35.

*Nelda Bishop*

BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Michael Mileski, in a field survey on November, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

MC #17; East Meander Corner between B-9 and C-9, T52N, R33W;

Originally established during U.S. Survey conducted by William Burt, D.S. in 1849 and monumented with a sugar maple post witnessed by a Sugar 12 N12°E 12 lks.

No subsequent record evidence was found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

MC #17; East Meander Corner between B-9 and C-9, T52N, R33W;

This corner was considered lost and reestablished on line at the proportionate distance between the N¼ corner of section 30 and the NE corner of section 30. This corner position falls in the Sturgeon River. A witness corner was established on the section line at a distance of 82.00 feet easterly of the proportioned meander corner. The witness corner is located approximately 33 feet east of the water's edge.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

MC #17; East Meander Corner between B-9 and C-9, T52N, R33W;

The witness corner described in Part B was monumented with a 1" (I.D.) x 36" galvanized iron pipe with cap stamped as to location projecting 6" above ground.

Set 7" spike	SW/side	13" Box Elder	N32°W	57.98'
Set 7" spike	W/side	9" Elm	N05°W	81.35'
Set 7" spike	E/side	13" Box Elder	N17°E	53.04'
Set 7" spike	S/side	13" Box Elder	S83°E	51.87'
		6' Steel fence post w/ yellow sign	South	2.0'

All of the above new bearing trees were marked with upper and lower blazes. The lower blaze was scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.



APPROVED BY LAND CORNER  
 345 OF 1990  
 Baraga County  
 12-17-98  
*[Signature]*

*[Signature]*

Signed by \_\_\_\_\_  
 Surveyor's Michigan License No. 39091

Date 28 Dec 1998