

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T52N R 33W</u>	<u>G2</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>3</u> T <u>52N</u> R <u>33W</u>	<u>10</u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
4. Lot No. <u>    </u> , Recorded Plat <u>    </u>		
5. Private Claims		

Register of Deeds Stamp & File  
Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5			4	●	3		2		1
3							●					
4	7		8			9		10		11		12
5												
6	18		17			16		15		14		13
7												
8	19		20			21		22		23		24
9												
10	30		29			28		27		26		25
11												
12	31		32			33		34		35		36
13												

I, Stephan J. Szyszkoski, in a field survey on Apr 18, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(G2) Quarter corner common to Sections 3 and 4. 1980 - K.L.Sackett reestablished the corner by single proportionate measurement between Section corners north and south. Corner falls in a deep east-west drain ditch. Set 1"IDx32" I.pipe 18.10' south of corner 225' west of C/L RR tracks. No other witnesses made.

(10-Sec. 3) South 1/16 corner between Sections 3 and 4. Established in 1980 by K.L.Sackett RLS midway and on line between corners to north and south. Set 1"IDx32" I.pipe with 4" alum. cap. 5" Tamarack N70E 31.5', 6" Tamarack N13W 42.2', 10" Tamarack S15W 8.3'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(G2) The 1980 witness monument was not recovered and is presumed to have been destroyed or is now deeply buried under a parking lot, which has been constructed over the corner position. Reestablished the corner by single proportionate measurement to the original record, on line between Section corners 2641.34' north and south.

(10-Sec. 3) Recovered the 1980 monument in good condition and at record bearing and distance from the N70E BT, in good condition. The other two BTS have been destroyed by road construction. Found the monument at record position between Section corner south and Quarter corner north. Accepted same as a careful and faithful establishment of the position of the corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(G2) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.	(10) Fd. 1"ID I.pipe with 4" alum. MDNR cap.
Set measuring nail in the side of:	Set measuring nail with MDNR tag in the side of:
3" Tam. N53E 173.70' mrkd "1/4S NBT"	11" Tamarack N28E 58.6' mrkd "1/16S BT"
4" Tam. N68E 136.16' do	10" Tamarack N59E 27.1' do
Parking area sign post S07W 164.55'	12" Tamarack N72E 32.0' do *
Distances above are to nail with MDNR tag.	5" Tamarack S02E 51.9' do
Chis "+" top N'y gate post N62W 197.8'	Set sq'd cedar post adjacent. Bearings are
Bearings are magnetic. Monument set flush with parking area surface.	magnetic. * denotes 1980 BT.

Signed by Stephan J. Szyszkoski



Date 11/27/07

Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities