

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	S ___ T ___ R ___	_____
2. Property Controlling in Section	S <u>5</u> T <u>52N</u> R <u>33W</u>	<u>6</u>
	S <u>5</u> T <u>52N</u> R <u>33W</u>	<u>9</u>
3. Miscellaneous Property in Sec.	S <u>5</u> T <u>52N</u> R <u>33W</u>	<u>13</u>
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

Feb 14 2007

I, Stephan J. Szyszkoski, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- (6-Sec. 5) Northeast 1/16 corner. Not established in the original survey.
- (9-Sec. 5) East 1/16 corner, Section 5. Not established in the original survey.
- (13-Sec. 5) Southeast 1/16 corner, Sec. 5. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (6-Sec. 5) Established the corner at the intersection of straight lines connecting opposite 1/16 corners. The position for the corner falls on the north bank of an E-W drainage ditch.
- (9-Sec. 5) Established the corner midway and on a straight line between Quarter corner 1316.38' east and Intersection of 1/4 lines 1316.38' west.
- (13-Sec. 5) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(6) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 5" Sugar N10E 55.7' mrkd "1/16S BT" 8" Ash N56E 30.6' do 18" Y.Birch S48W 53.4' do 8" Ash N39W 48.3' do Squared Balsam post adjacent. Bearings are magnetic. Distances are to nail with tag.	(9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 9" Ash N21E 38.7' mrkd "1/16S BT" 13" Sugar S84E 19.0' do 4" Ash S21W 33.8' do 9" Maple N22W 36.1' do Sq'd Ash post adjacent. Bearings are magnetic. Distances are to nail with tag.	(13) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 6" Ash N19E 17.1' mrkd "1/16S BT" 12" Maple N73E 42.6' do 8" Ash S16E 20.4' do 11" Ash S48W 23.1' do Sq'd Ash post adjacent. Bearings are magnetic. Distances are to nail with tag.
---	---	---

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 2/20/07

