

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S <u>3</u> T <u>52N</u> R <u>33W</u>	<u>11</u>
3. Miscellaneous Property in Sec.	S <u>21</u> T <u>52N</u> R <u>33W</u>	<u>15</u>
	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4			3		2				
3							●					
4	7	8	9			10		11				
5												
6	18	17	16			15		14				
7												
8	19	20	21			22		23				
9						●						
10	30	29	28			27		26				
11												
12	31	32	33			34		35				
13												

I, Stephan J. Szyszkoski, in a field survey on June 25, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 (11-Sec. 3) Southwest 1/16 corner, Section 3. Not established in the original survey. Found no subsequent record.
 (15-Sec. 21) West 1/16 corner between Sections 21 and 28. Not established in the original survey.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (11-Sec. 3) Established the corner at the intersection of straight lines connecting opposite 1/16 corners. From the position thus established, I found a 2" ID iron pipe, set by persons unknown, S37E 20.1' distant, which I did not accept as marking the position for the corner.
 (15-Sec. 21) Established the corner midway and on the section line between Section corner 1322.11' west and Quarter corner 1322.11' east. The position for the corner falls in a mowed ditch south of a farm lane. Set the monument cap flush with the surface of the ground.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (11) Set 1" IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 9" Maple S40W 24.5' mrkd "1/16S BT"
 12" double Sugar N64E 20.6' do
 5" Maple S71W 28.2' do
 6" Sugar N12W 25.2' do
 Set sq'd cedar post adjacent. Bearings are magnetic.
 (15) Set 1" IDx32" I.pipe with 4" alum. MDNR cap, flush with ground. Set measuring nail/MDNR tag in:
 8" Sugar N33E 48.3' mrkd "1/16S BT"
 12" Ash S06W 26.0' do
 9" Sugar N49W 73.4' do
 S83E 40.2' utility pole nail/tag only
 Set cedar post adjacent. Bearings are magnetic.

Signed by Stephan J. Szyszkoski



Date 11/27/07

Surveyor's Michigan License No. 33986