

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____	_____
	S <u>5</u> T <u>52N</u> R <u>33W</u>	<u>12</u>	_____
	S <u>5</u> T <u>52N</u> R <u>33W</u>	<u>16</u>	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims	16 Feb 15 2007		
	12 Feb 14 2007		

Register of Deeds Stamp & File Number

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3				●									
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- (12-Sec. 5) South 1/16 corner, Sec. 5. Not established in the original survey.
- (16-Sec. 5) East 1/16 corner between Sections 5 and 8. Established in 1977 by K.L.Sackett RLS at "fence corner which is on line between section corner east and quarter corner west". Set 1"IDx36" iron pipe with 4" aluminum cap. No available witnesses. Corner falls in marshy field.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (12-Sec. 5) Established the corner midway and on a straight line between Quarter corner 1316.79' south and Intersection of 1/4 lines 1316.79' north.
- (16-Sec. 5) Found the 1977 monument as described, in good condition, in accord with Section and Quarter corners east and west. Left the monument in place.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|--|
| <ul style="list-style-type: none"> (12) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 6" Balsam East 0.9' mrkd "1/16S BT" 5" Spruce S17E 18.7' do 9" Maple S49W 18.4' do 5" Spruce N54W 17.5' do "T" fence post N78E 26.4' Barbed wire fnc corner in tree S34E 21' Bearings are magnetic. Dist. to trees are to nail with tag. | <ul style="list-style-type: none"> (16) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nails in: 8" Poplar N65W 66.3' mrkd "1/16S BT" Old fence post leaning E'ly S18W 58.7' Old fence post leaning E'ly S09W 7.7' Squared Ash post N23E 1.55' Bearings are magnetic. Distances are to nail with tag. |
|--|--|



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 2/20/07