

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>21</u> T <u>52N</u> R <u>33W</u>	<u>5</u>
	S <u>21</u> T <u>52N</u> R <u>33W</u>	<u>8</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 12/06/2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(5-Sec. 21) North 1/16 corner, Section 21. Not established in the original survey.

(8-Sec. 21) West 1/16 corner, Section 21. 1907 - Established by W.W. Stockly, Engineer, midway and on a straight line between Quarter corner 19.98 chains west and Center of Section 19.98 chains east. No mention was found in the field notes describing the monument or accessories.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(5-Sec. 21) Established the corner midway and on a straight line between Center of Section 1313.48' south and Quarter corner 1313.48' north.

(8-Sec. 21) At the position for the corner, midway and on a straight line between Quarter corner 1318.49' west and Center of Section 1318.49' east, I found a post point rotted off at the water table and sound below. Removed the post point, probably the remains of the Stockly monument, and placed a monument as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(5) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 12" Maple N43E 24.75' mrkd "1/16S BT"
 13" Hemlock S68E 7.3' do
 14" Hemlock S42W 2.1' do
 6" Cedar N38W 18.15' do
 Set sq'd post adjacent. Bearings magnetic.

(8) Set 1"IDx48" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 8" Cedar N42E 17.9' mrkd "1/16S BT"
 6" Cedar S82E 22.5' do
 7" Cedar S64W 8.8' do
 9" Cedar N50W 6.8' do
 Set sq'd post adjacent. Bearings magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 09/03/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities