

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 52N R 33W	C7
	T 52N R 33W	C6
2. Property Controlling in Section	S T R	
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18	●	17		16		15		14		13		
7		●											
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on C7 12/03/2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C7) Corner common to Sections 17-18-19-20. 1849 - Established by Wm.A.Burt Deputy Surveyor. Set cedar post. Hemlock 10 N31W 7 links, Hemlock 6 S20E 9 links.

(C6) Quarter corner common to Sections 17 and 18. 1849 - Established by Wm.A.Burt Deputy Surveyor, midway and on the Section line between Section corners 40.00 chains north and south. Set cedar post. Hemlock 30" N20E 13 links, Hemlock 14" S78W 18 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C7) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner by double proportionate measurement to the original record between Section corners 5270.5' north and south (80.00 ch. GLO), Quarter corner 2641.62' west (40.00 ch. GLO), and Quarter corner 7963.65' east (120.59 ch. GLO).

(C6) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner midway and on the Section line between Section corners 2635.25' north and south, being proportionate to the original record.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C7) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 8" Cedar N55E 20.3' mrkd "S17 NBT"  
 6" Sugar S40E 2.7' "S20 NBT"  
 13" Y.Birch S35W 35.3' "S19 NBT"  
 16" Maple S86W 13.2' "S19 NBT"  
 Set sq'd post adjacent. Bearings magnetic.

(C6) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 8" Sugar N01W 17.3' mrkd "1/4S NBT"  
 5" Sugar N70E 25.3' do  
 7" Sugar S15W 29.7' do  
 6" Sugar N38W 8.2' do  
 Set sq'd post adjacent. Bearings magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 09/03/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities