

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____ T <u>52N</u> R <u>33W</u>	<u>C8</u>
2. Property Controlling in Section	S <u>17</u> T <u>52N</u> R <u>33W</u>	<u>D6</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		●		16		15		14		13		
7													
8	19		●		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on D6 12/10/2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(D6) Center of Section 17. Not established in the original survey.

(C8) Quarter corner common to Sections 19 and 20. 1849 - Established by Wm.A.Burt Deputy Surveyor midway and on the Section line between Section corners 40.00 chains north and south. Set Elm post. Elm 10" S65E 6 links, Sugar 18" N58W 39 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(D6) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.

(C8) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner midway and on the Section line between Section corners 2635.22' north and south, being proportionate to the original record.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D6) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 9" Y.Birch N53E 9.4' mrkd "C1/4 BT"
 5" Sugar S23W 25.4' do
 8" Y.Birch N70W 4.5' do
 4" Cedar N24W 8.0' do
 Set sq'd post adjacent. Bearings magnetic.

(C8) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 7" Ash N55E 23.3' mrkd "1/4S NBT"
 4" Ash S82E 14.5' do
 5" Ash S18W 16.0' do
 5" Ash N76W 2.7' do
 Set sq'd post adjacent. Bearings magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 09/03/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities