

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 52N R 33W	E6
	T 52N R 33W	E7
2. Property Controlling in Section	S T R	
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on E6 06/30/2008 and E7 06/30/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E6) Quarter corner common to Sections 16 and 17. 1849 - Established by Wm.A.Burt Deputy Surveyor midway and on line between Section corners 40.00 chains north and south. Set Tamarack post. Tamarack 4" East 1 link, Tamarack 6" S18W 17 links.

(E7) Corner common to Sections 16-17-20-21. 1849 - Established by Wm.A.Burt Deputy Surveyor. Set Tamarack post. Tamarack 5" N21W 42 links, Tamarack 7" S64E 34 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E6) The original post and accessories were not recovered. Any evidence of the original corner on the ground has been destroyed by subsequent construction of a deep drainage ditch which runs along the line between Sections 16 and 17. Reestablished the corner midway and on the line between Section corners 2639.74' north and south, being proportionate to the original record. The position for the corner falls in the ditch and was not monumented. Established a Witness Corner 30.00' west of the corner position and on the E-W 1/4 line of Section 17.

(E7) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner by double proportionate measurement to the original record between Quarter corner 7949.85' west (120.38 ch. GLO), Quarter corner 2655.42' east (40.21 ch. GLO), Section corner 5279.46' north (80 ch. GLO), and Quarter corner 2639.71' south (40 ch. GLO). The position for the corner falls at the water's edge on the east side of a N-S drainage ditch.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E6) Set 1"IDx32" I.pipe with 4" alum. MDNR cap 30.00' West of the corner position on the E-W 1/4 line of Sec. 17 for a Witness Corner. Set measuring nail with MDNR tag in the side of: 10" Maple in clump N58W 2.85' mrkd "WC BT" 17" Maple S07E 26.6' do 6" Balsam S30W 17.4' do Set sq'd cedar post S78E 0.65' distant Bearings are magnetic.

(E7) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 10" Tamarack N36E 59.9' mrkd "S16 NBT" 11" Tamarack N69E 43.2' do 9" Tamarack S09E 62.5' "S21 NBT" Set a sq'd post S77E 1.1' distant. Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 09/04/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities