

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>19</u> T <u>52N</u> R <u>33W</u>	<u>2</u>
	S <u>19</u> T <u>52N</u> R <u>33W</u>	<u>B8</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7	●												
8	●	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 12/05/2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(2-Sec. 19) East 1/16 corner between Sections 18 and 19. Not established in the original survey.

(B8) Center of Section 19. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(2-Sec. 19) Established the corner midway and on the Section line between Quarter corner 1320.81' west and Section corner 1320.81' east.

(B8) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(2) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.  
 Set measuring nail with MDNR tag in the side of:  
 8" twin Sugar N25W 8.9' mrkd "1/16S BT"  
 8" Maple N60E 5.65' do  
 4" Sugar S28E 25.7' do  
 9" twin Maple S65W 13.6' do  
 Set sq'd post adjacent. Bearings magnetic.

(B8) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.  
 Set measuring nail with MDNR tag in the side of:  
 5" Sugar S66E 13.8' mrkd "C1/4 BT"  
 6" Sugar S13E 19.0' do  
 8" Sugar N75W 18.3' do  
 15" Hemlock N26W 35.5' do  
 Set sq'd post adjacent. Bearings magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 09/03/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities