

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 52N R 33W	D7
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 17 T 52N R 33W	7
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Stephan J. Szyszkoski, in a field survey on 7 06/30/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(D7) Quarter corner common to Sections 17 and 20. 1849 - Established by Wm.A.Burt Deputy Surveyor, midway and on the Section line between Section corners 40.19 chains east and west. Set Tamarack post. Tamarack 6" N58E 40 links, Tamarack 6" S34W 25 links.

(7-Sec. 17) North 1/16 corner between Sections 16 and 17. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(D7) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner midway and on the Section line between Section corners 2654.12' east and west, being proportionate to the original record.

(7-Sec. 17) Established the corner midway and on the Section line between Section corner 1319.87' north and Quarter corner 1319.87' south. The position for the corner falls in a deep N-S drainage ditch and was not monumented. Established a Witness Corner on the E-W 1/16 line, 30.00' west of the 1/16 corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D7) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:	(7) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. The monument is 30.00' west of the corner position as described above. Set measuring nail with MDNR tag in the side of:
4" B.Ash S86E 15.7' mrkd "1/4S NBT"	13" Spruce N41E 6.5' mrkd "WC BT"
13" twin Maple S40W 7.4' do	10" Spruce S05W 11.25' do
6" B.Ash N79W 18.8' do	20" Maple S73W 19.3' do
13" Maple North 20.7' do	10" Spruce N57W 28.0' do
Set sq'd post adjacent. Bearings magnetic.	Set sq'd post adjacent. Bearings magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 09/03/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities