

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 52N R 33W	F7
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 09/27/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(F7) Quarter corner common to Sections 16 and 21. 1849 - Established by Wm.A.Burt Deputy Surveyor midway and on the Section line between Section corners 40.21 chains east and west. Set tamarack post. Tamarack 4" N8E 26 links, Tamarack 4" S44W 7 links. 1907 - Original corner recovered by Engineer W.W.Stockly and used for his subdivision of Section 21. No description of monument or accessories.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F7) Found the remains of the 1849 tamarack post 4" dia. 2' long, in good condition below the water table, with distinctive long clean axe strokes. Found the original BT tamaracks S39W 5.2' in good condition with "1/4S" visible and N9E 18.0' a rotted stump with no markings visible. Found two smaller wooden post points adjacent. One likely that of W.W.Stockly, the other, quite small and ill-made, likely left later by a forester. I accept the 4" post point as the original corner post and replace it with a monument as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F7) Set a 1"IDx6' iron pipe (in two connected pieces) with 4" alum. MDNR cap. Set measuring nail with PS tag #31595 in the side of:
 8" Tamarack N32E 19.3' mrkd "S16 NBT"
 8" Tamarack N77E 16.2' do
 8" Tamarack N38W 23.8' do
 8" Tamarack S68W 4.9' "S21 NBT"
 Bearings are magnetic. Set sq'd post with Property Corner poster affixed, adjacent.



Signed by *Stephan J. Szyszkoski* Date 10/08/2008
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities