

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>21</u> T <u>52N</u> R <u>33W</u>	<u>F8</u>
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 10/21/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(F8) Center of Section 21. Not established in the original survey. 1907 - Established by W.W.Stockly, Engineer, during his subdivision of Section 21 for J.S.Morrison. Mr. Stockly set Center of Section 21 40.10 chains north of South 1/4 corner and 39.95 chains east of West 1/4 corner. This position has been perpetuated by local landowners.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F8) Found old corner fence post at the intersection of ancient fencelines N-S-E-W, the post being 40.066 chains north of the South 1/4 corner and 39.954 chains east of West 1/4 corner of Section 21. Recovered Mr. Stockly's post at the West 1/16 corner of Section 21, 1318.50' west, midway and on a straight line between this position and the West 1/4 corner. The post is located 17.3' west of a straight line between north and south 1/4 corners and 10.0' north of a straight line between east and west 1/4 corners. I accept the post as a careful and faithful determination of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F8) Set 1"IDx32" I.pipe with 4" alum. MDNR cap at the position of old corner fence post.
 Set measuring nail with MDNR tag in the side of:
 7" Sugar N43E 3.2' mrkd "C1/4 BT"
 12" Sugar S37E 17.6' do
 12" Sugar S51W 21.2' do
 9" Sugar N63W 40.4' do
 Set sq'd cedar post adjacent.
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 10/28/2008
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities