

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

BARAGA

FOR CORNERS OF --	LOCATED IN --	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>53</u> N. XX R. <u>30</u> W	A12
2. PROPERTY CONTROLLING IN SECTION <u>31</u>	T. <u>53</u> N. XX R. <u>30</u> W	3 & 10
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ R. _____ E. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER _____

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on May 17 19 73, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:**
- Corner A12:** Wood Post (not found)
Cedar 8 S65E 12 " "
Fir 6 N39W 21 " "
 - Corner 3:** Not established in original survey and by approximation only, subsequently. Found a 2" x 2" x 5' squared cedar post N25½°E 46.5 ft.
 - Corner 10:** Not established in original survey nor subsequently, apparently.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**
- Corner A12:** Re-established on line between sec. corners 40.00 ch. to N and to S. Found a 12" cedar with blazes on 4 sides S44°E 14.6 ft. for an approximate corner.
 - Corner 3:** Established on line between sec. corner 20.00 ch. N and 1/4 corner 20.00 ch. S.
 - Corner 10:** Established on line between sec. corner 20.00 ch. S and 1/4 corner 20.00 ch. N.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**
- Corner A12:** 1" I.D. x 36" iron pipe with 4" aluminum cap.
Cedar 5 N27°W (mag.) 1.4 ft. "1/4S, NBT"
Cedar 6 N89°E (mag.) 15.3 ft. "1/4S, NBT"
Cedar 5 S24°W (mag.) 17.6 ft. "1/4S, NBT"
Also squared & scribed a 5" cedar 0.9 ft. West.
 - Corner 3:** 3"x3"x5½' squared cedar post scribed "1/16, 31, 36"
Cedar 5 S19°W (mag.) 2.5 ft. "1/16S, BT"
Cedar 12 N32°W (mag.) 14.9 ft. "1/16S, BT"
 - Corner 10:** 4"x4"x5½' squared cedar post scribed "1/16, 31, 36"
Cedar 12 S79°W (mag.) 10.5 ft. "1/16S, BT"
Cedar 15 S35°E (mag.) 12.2 ft. "1/16S, BT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)
FOR STATE AND UNITED STATES AGENCIES: _____

SIGNED BY _____ DATE _____
APPROVED AND SIGNED BY Arthur O. Enger DATE October 23, 1973
Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581
Form No. ML M736
FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN 28 1973
DISTRIBUTED BY MICHIGAN SOCIETY OF REGISTERED LAND SURVEYORS

