

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 53 N.R. 30-31 W

Baraga COUNTY


DESCRIPTION OF CORNER Section Corner for Secs. 25, 36 T53N R3W & 30, 31 T53N R3W

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 7/21/65 with J. Magnuson

WITNESSES TO CORNER..... 20" Hemlock (S36 NBT), S 44° W, 35½ Lks.

12" Hemlock (S25 NBT), N 19° W, 60½ Lks.



AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was replaced from (4) four Original Hemlock BT's two are green and growing to NW and SW, BT to SE is a dead snag, to NE is dead and down.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 9/13/1965
REGISTERED LAND SURVEYOR