

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #	
<b>1. Public Land Survey</b>	T <u>53N</u> R <u>30W</u>	<u>C12</u>	
	T <u>    </u> R <u>    </u>	<u>    </u>	
	T <u>    </u> R <u>    </u>	<u>    </u>	
	T <u>    </u> R <u>    </u>	<u>    </u>	
<b>2. Property Controlling in Section</b>	S <u>31</u> T <u>53N</u> R <u>30W</u>	<u>5</u>	
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>	
<b>3. Miscellaneous Property in Sec.</b>	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>	
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

C12 Jan 28 2002  
 5 Jan 03 2002

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 2002 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**A. Description of original monument and accessories and/or subsequent restoration:**  
 (C12) Quarter corner common to Sections 31-32. Established in 1846 by Wm. Ives: South between 31 & 32...40.00 Set qr. Section post. Cedar 15 N51E 12, Y.Birch 10 S88W 18...43.50 Descend bank of former coast of bay about 15 feet SSW.  
 (5-Sec. 31) North 1/16 corner, Section 31. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(C12) Recovered an old 1.25"x1.25" angle iron fence post at record bearing and distance from the probable remains of the Cedar BT, now a rotted stump of proper size with old axe blaze and flattened overgrowth found at the root crown facing the corner. No scribe marks visible as the face has rotted away. Also recovered possible Y.Birch stump hole at record bearing and distance. The distance south from the fence post to Descend checks with the record and would not check east or west of this position on account of the acute angle of the coast. Distance north to Section corner is 2643.7'. Old overgrown blazes on 4 trees face this position as does a tag on a 26" Sugar S63E stamped: "Roy Bell 1-27-65 1/4 cor". Accepted the fence post as a careful and faithful perpetuation of the position of the original corner and replaced it with a monument described below.  
 (5-Sec. 31) Established the corner midway and on a straight line between Quarter corner 1320.70' north and Center of Section (unmonumented in this survey) 1320.70' south.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(C12) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed and scribed:	(5) Set 1"IDx32" I.pipe with 4" MDNR cap. Blazed and scribed:
21" Cedar N04E 27.8'      "1/4S N8T"	6" Hemlock North 7.6'      "1/16S 8T"
10" Maple N65E 32.0'      do	9" Hemlock N70E 7.6'      do
17" Maple S12E 18.9'      do	11" Hemlock S12W 13.5'      do
7" Cedar N62W 17.7'      do	11" Maple N88W 7.2'      do
Set squared cedar post and the iron fence post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.	Set squared cedar post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski Date 3/19/02  
 Surveyor's Michigan License No. 33986