

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

BARAGA

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 53 N. R. 31 E. W.	J 13
2. PROPERTY CONTROLLING IN SECTION 35	T. 53 N. R. 31 E. W.	16
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, **Arthur O. Enger** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were in a field survey on **May 17, 1973**, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current code of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey of \_\_\_\_\_ 19\_\_\_\_ found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner J13: Wood post (not found)**  
 Sugar 12 N5W 33 " "  
 Maple 16 S8E 39 " "  
 Found a 3"x3"x5 1/4' cedar post .075 ch. S for approx. corner

**Corner 16: Not established in original survey nor subsequently, apparently.**

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner J13: Re-established on line between original sec. corners 40.00 ch. W and 41.10 ch. E. Measurements on this line to a stream crossing indicate the probability of a mistake in the original measurement somewhere in the W 3/4 of the mile. No sure way to tell exactly where the mistake was made, but local property owners and other surveyors appear to have adopted a 40.00 ch. West half-mile, so I accepted that premise also.**

**Corner 16: As a consequence of the condition noted above, I placed the entire 1.10 ch. excess measurement between the 1/4 cor. and the E 1/16 cor., establishing the E 1/16 cor. on line between 1/4 cor. 21.10 ch. W and sec. corner 20.00 ch. E.**

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner**

**Corner J13: 1" I.D. x 36" iron pipe with 4" aluminum cap.**  
 Cedar 8 N11°W (mag.) 12.0 ft. "1/4S, NBT"  
 Red Maple S36°W (mag.) 15.4 ft. "1/4S, NBT"

**Corner 16: 3"x3"x5 1/4' squared cedar post scribed "1/16, 2, 35"**  
 Hemlock 12 S67°E (mag.) 5.9 ft. "1/16S, BT"  
 Hemlock 8 S78°W (mag.) 29.4 ft. "1/16S, BT"

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_

DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_

*Arthur O. Enger*  
 \_\_\_\_\_  
**Arthur O. Enger**

DATE \_\_\_\_\_

**Michigan Department of Natural Resources**

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

13581

Form No. MLM735  
 DOUBLE COPY - BRONZE - 1970

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTERED LAND SURVEYORS  
 DISTRIBUTED BY MICHIGAN SOCIETY OF REGISTERED LAND SURVEYORS

