

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Baraga
 (County)

Located In:

Corner Code #

- | | | |
|------------------------------------|-------------|---------------|
| 1. Public Land Survey | T 53N R 31W | MC N. of K12 |
| | T 53N R 31W | ANC N. of J13 |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Nov 27 2001

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													


A. Description of original monument and accessories and/or subsequent restoration:
 (MC N. of K12) Witness corner to the record position of the Meander Corner between Sections 35 and 36. The original Meander Corner (22.39 chains north of the 1/4 corner) and its accessory were not recovered.
 (ANC N. of J13) Auxilliary Meander Corner on the N-S 1/4 line of Section 35. Remonumented in 1989 by Ewart C. Muller, RLS. See description in Liber 4 of LCRCs, Page 188, Baraga County Records. 5/8"x24" rerod with cap 22' +/- from water's edge. R.Mpl clump S19W 17.50', Cedar 9 S24W 75.20', Cedar 9 S80E 89.40'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(MC N. of K12) Established a witness corner on the section line between 35 & 36 21.0606 chains (1390.00 feet) north of the Quarter corner K12, 1.33 chains southerly of the record position of the Meander Corner. The section line is a line produced through the Quarter corner and the Southwest corner of Section 36.
 (ANC N. of J13) Mr. Muller's monument was not recovered. Reestablished the 1989 position at record bearing and distance from the 1989 witnesses, all recovered in good condition. There were no markings on or measuring nails in the 1989 witnesses. This monument is 1222.74' north of J13.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(MC) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed and scribed: 7" W.Spruce N02E 43.3' "MC NBT" 6" B.Spruce S65E 12.7' do 14" W.Pine S10W 19.9' do 7" Cedar S45W 25.2' do Set squared cedar post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.	(ANC) Set 1"IDx32" I.pipe with plastic cap stamped "MICH DNR LS33986". Made small BH blaze with 4 axe marks on the trees at root crown: R.Maple clump S17W 17.5' 9" Cedar S26W 75.2' 9" Cedar S78E 89.4' Bearings are magnetic.
---	---



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 3/19/02