

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Baraga	Located In:	Corner Code #	
(County)			
1. Public Land Survey	T <u>53N</u> R <u>31W</u>	K12	
	T <u>53N</u> R <u>31W</u>	M11	
	T <u> </u> R <u> </u>		
	T <u> </u> R <u> </u>		
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>		
	S <u> </u> T <u> </u> R <u> </u>		
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>		
	S <u> </u> T <u> </u> R <u> </u>		

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

M11 Aug 30 2001
 K12 Aug 28 2001

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5		4		3		2		1		
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (K12) Quarter corner common to Sections 35-36. Reestablished in 1989 by Ewart C. Muller LS: 5/8" x 24" rerod with aluminum cap stamped 1/4 S, 35, 36 and 3"x3"x5' squared post. NBTs: Cedar 9 N51W 18.45', Cedar 9 N32E 2.65', Cedar 10 S13E 10.80'. Corner recorded in L4 of LCRCs P179, Baraga Co. Records.
 (M11) Corner common to Sections 25-36 T53N-R31W and 30-31 T53N-R30W. Remonumented in the original position by F.J. Bray RLS in 1965. 1" iron pipe with 4" aluminum cap. 20" Hemlock S44W 35.5 links, 12" Hemlock N19W 60.5 links. Original bearing trees described by Wm. Ives in 1846: Hemlock 12 S85W 13, Hemlock 8 N40W 07. Corner recorded in L2 of LCRCs, P299, Baraga Co. Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K12) Found the 1989 monument as described, in good condition and at record bearing and distance from the 1989 accessories, all in good condition. The 1989 witness trees were felled, the cuts made above the lower blaze, to facilitate GPS observations at this corner. Made new witnesses as described below. The monument is accepted as a careful and faithful reestablishment of the position of the corner.
 (M11) Recovered the 1965 monument as described, in good condition and at record bearing and distance from the original bearing trees noted above, the NW with scribing visible, the SW with blazes overgrown. The 1965 Hemlock SW was also found at record bearing and distance and leaning toward the corner. The 1965 NW Hemlock is windthrown. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K12) Found 5/8" rebar with aluminum cap appropriately marked. Blazed and scribed the following: 14" Hemlock N09W 10.4' 12" Cedar S24E 25.3' 18" Hemlock S14W 20.7' 9" Cedar N66W 32.2' Set squared cedar post adjacent. Bearings are magnetic. Distances to notch in lower blaze.	"1/4S NBT" do do do	(M11) Found 1" ID 1-pipe with 4" alum. Michigan Dept. of Conservation tablet from which: 15" Hemlock 08T N36W 4.6' w/scribing 24" Hemlock 08T S87W 8.3' overgrown 18" Hemlock N8T S51W 22.5' w/scribing 9" Y.Birch N56E 38.3' "S30 NBT" Bearings are magnetic. Distances to notch in lower blaze.
--	------------------------------	--



Signed by Stephan J. Szyszkoski Date 3/19/02
 Surveyor's Michigan License No. 33986